

15-071-20233-00-00

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202

Greeley County, Sec. 34 Twp. 19S Rge. 39 E/W
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines
C SW/4


Lease Owner Cities Service Company
Lease Name Toadvine A Well No. 1
Office Address 3545 N.W. 58th St., Okla. City, OK 73112
Character of Well (Completed as Oil, Gas or Dry Hole) Dry Hole

Date Well completed 6-8-1982
Application for plugging filed 5-13-1982
Application for plugging approved 5-17-1982
Plugging commenced 6-7-1982
Plugging completed 6-8-1982
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Steve Durrant
Producing formation None Depth to top Bottom Total Depth of Well 2910'
Show depth and thickness of all water, oil and gas formations.



Locate well correctly on above Section Plot

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Winfield	Dry	2820'	2826'	8-5/8"	456'	None
				4-1/2"	2909'	2020'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Set CIBP @ 2810 w/9' cmt (1 sx) on top of plug. Top of cmt @ 2801'; loaded hole w/mud; Shot 4-1/2" csg off @ 2020'; came free. Spotted 25 sx; plug from 2020-1950; spotted 40 sx; plug from 1950-402'; pulled pipe out of hole; spotted 10 sx; plug from 40'-4' below surface.


(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor DACO, Inc.

STATE OF Oklahoma COUNTY OF Oklahoma, ss.
Verlin Meier (employee of owner) or (owner or operator)
of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Verlin Meier Verlin Meier
Prod. Region Mgr.

SUBSCRIBED AND SWORN TO before me this 20th day of June, 1982
Oliver E. Mines
Notary Public.



Rec. 6/25/82
KCC

KANSAS DRILLER'S LOG

15-071-20233-00-00

LEASE: TOADVINE "A" #1
 OWNER: CITIES SERVICE COMPANY
 SPUD: 4-28-81
 COMP: 5-01-81

LOCATION: C SW/4
 SECTION 34-19S-39W
 GREELEY COUNTY, KANSAS
 CASING: 8 5/8" SET @ 456'
 4 1/2" SET @ 2909'

Soil, Sand & Clay	457
Shale	1455
Shale & Shells	2090
Shale - Sand	2450
Shale & Shells	2660
Shale	2830
Sand & Shale	2910
R.T.D.	2910

STATE OF KANSAS)
) ss.
 COUNTY OF SEDGWICK)

I, William C. Wakefield, do hereby certify that this is a true and correct Driller's Log on the TOADVINE "A" #1, located C SW/4 SECTION 34-19S-39W, Greeley County, Kansas, as shown by the daily drilling reports.

EARL F. WAKEFIELD, INC.

RECEIVED
 STATE CORPORATION COMMISSION

By William C. Wakefield

MAY 17 1982

Subscribed and Sworn to before me this 8th Day of May, 1981.

My Appointment Expires:
 October 28, 1984

Carol J. Noel
 Carol J. Noel Notary Public

