

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 130 S. Market, Room 2078
 Wichita, KS 67202

WELL PLUGGING RECORD
 K.A.R.-82-3-117

API NUMBER 15-071-20657-00-00
 LEASE NAME REXFORD
 WELL NUMBER #1-30
3960 Ft. from S Section Line
1980 Ft. from E Section Line

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

LEASE OPERATOR MIDWESTERN EXPLORATION CO.
 ADDRESS PO BOX 1884, LIBERAL, KS 67905-1884
 PHONE (316) 624-3534 OPERATORS LICENSE NO. 5263

SEC. 30 TWP. 19 RGE. 39 (E) or (W)
 COUNTY GREELEY
 Date Well Completed 10/11/96
 Plugging Commenced 12/15/98
 Plugging Completed 12/15/98

Character of Well GAS
 (Oil, Gas, D&A, SWD, Input, Water Supply Well)
 The plugging proposal was approved on DECEMBER 2, 1998 (date)
 by DAVID P. WILLIAMS (KCC District Agent's Name).

Is ACO-1 filed? YES If not, is well log attached? _____

Producing Formation UPPER WINFIELD Depth to Top 2838 Bottom 2850 T.D. 2850
 Show depth and thickness of all water, oil and gas formations.


OIL, GAS OR WATER RECORDS | CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
UPPER WINFIELD	GAS	0	252'	8-5/8"	252'	0
		0	2832'	4-1/2"	2832'	0
		2832'	2850'	2-7/8"	18'	0

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from feet to feet each set.
Mixes 300# hulls with 10 bbls fresh water & pumped down casing. Mixed 100# hulls with 140 sks 60/40 poz with 6% gel cement & pumped down casing. Well loaded & pressured to 500 psig with 28 bbls cement in hole. Tied to 8-5/8" casing & pressured immediately to 500# psig. Cut off 8-5/8" casing head & 4-1/2" pipe 5' below ground level. Welded cap on 8-5/8" casing. Backfill hole.

Name of Plugging Contractor N/A License No. 09-07-99
 Address _____
 NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: MIDWESTERN EXPLORATION CO.
 STATE OF KANSAS COUNTY OF SEWARD, ss.

CHUCK REDMON (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above-described well as filed the the same are true and correct, so help me God.
 (Signature) Chuck Redmon



(Address) PO BOX 1884, LIBERAL, KS 67905-1884

AND SWORN TO before me this 3rd day of September, 19 99
Virginia Means
 Notary Public
 My Commission Expires: March 16, 2003