

15-071-20232-00-00


STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to  
Conservation Division  
State Corporation Comm.  
245 North Water  
Wichita, KS 67202

Greeley County, Sec. 21 Twp. 19S Rge. 39 R/W  
Location as "NE/CNW $\frac{1}{4}$ /SW $\frac{1}{4}$ " or footage from lines  
C NW/4 SE/4

Lease Owner Cities Service Company  
Lease Name Kuttler C Well No. 1  
Office Address 3545 N.W. 58th St., Oklahoma City, OK 73112  
Character of Well (Completed as Oil, Gas or Dry Hole) Dry Hole



Locate well correctly on above Section Plat

Date Well completed 5-24 1982  
Application for plugging filed 5-13 1982  
Application for plugging approved 5-17 1982  
Plugging commenced 19  
Plugging completed 5-24 1982  
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Clarence Thomas  
Producing formation None Depth to top          Bottom          Total Depth of Well 2935  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Winfield	Dry	2857'	2867'	8-5/8"	413	413'
				4-1/2"	2934	1620'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from          feet to          feet for each plug set.

Set CIBP @ 2845' w/9' cmt plug on top @ 2834'; Shot pipe off @ 1620'; spot 25 sx plug @ 1620'; spot 40 sx plug 463-363'; spot 10 sx plug from 40'-4' below surface.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Daco, Inc.

STATE OF Oklahoma COUNTY OF Oklahoma, ss.  
Verlin Meier (employee of owner) or (owner or operator)  
of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Verlin Meier Verlin Meier  
Prod. Region Mgr  
3545 N.W. 58th - Oklahoma City, OK 73112  
(Address)

SUBSCRIBED AND SWORN TO before me this 22<sup>nd</sup> day of June, 19 82

My commission expires July 10, 1984  
         Notary Public.



Rec. 6/25/82  
KCC

JOHNSON

15-071-20232-00-00  
Drilling Company, Inc.



OFFICES IN

EVANSVILLE, INDIANA  
TEL. (812) 424-8291  
OKLAHOMA CITY, OKLAHOMA  
TEL. (405) 943-7667  
LIBERAL, KANSAS  
TEL. (316) 624-7731

REPLY TO:

3535 N.W. 58th, Suite 710  
Oklahoma City, Oklahoma 73112

April 29, 1981

CITIES SERVICE COMPANY  
P.O. BOX 686  
ULYSSES, KANSAS 67880

ATTEN: J.K. RUSSELL

DRILLERS LOG FOR:

0' - 414'  
414' - 1650'  
1650' - 1995'  
1995' - 2930'

KUTTNER C #1

Clay and Sand  
Sand and Shale  
Shale  
Lime and Shale

JOHNSON DRILLING COMPANY, INC.

SIGNED BY:

  
\_\_\_\_\_  
CLAUDE D. MOORE      MANAGER

STATE OF OKLAHOMA  
COUNTY OF OKLAHOMA

Subscribed and sworn to before me this 29th day of April, 1981.

  
\_\_\_\_\_  
NOTARY PUBLIC

My Commission Expires: \_\_\_\_\_  
My Commission Expires May 14, 1984

RECEIVED  
STATE CORPORATION COMMISSION

MAY 17 1982

CONSERVATION DIVISION  
Wichita, Kansas