


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

Greeley County, Sec. 17 Twp. 19S Rge. (E) 39 (W)

NORTH



Locate well correctly on above
Section Plat

Location as "NE/CNW/SW" or footage from lines _____
Lease Owner Hadson Oil & Gas Company
Lease Name Schmidt Unit Well No. 1
Office Address 316 Oklahoman Building, Oklahoma City, Okla.
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed September 21 19 63
Application for plugging filed September 21 19 63
Application for plugging approved September 21 19 63
Plugging commenced September 21 19 63
Plugging completed September 21 19 63
Reason for abandonment of well or producing formation _____

If a producing well is abandoned, date of last production _____ 19 _____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well W. L. Nichols
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 2932 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	203'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled with mud 2932' to 222'
222' with 25 sacks cement
5' off top with 15 sacks cement

RECEIVED
STATE CORPORATION COMMISSION

OCT 28 1963

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Earl F. Wakefield
Address 515 Union Center Building, Wichita, Kansas

STATE OF Kansas, COUNTY OF Seward, ss. _____
(employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Donald W. Jackson
1411 N. Cortina Liberal Kan
(Address)

SUBSCRIBED AND SWORN to before me this 26 day of October, 19 63

Albert S. Shantz
Notary Public.

My commission expires 1-23-66



15-071-00027-00-00

LEASE: SCHMIDT UNIT NO. 1
OWNER: HADSON OIL & GAS COMPANY
CONTRACTOR: EARL F. WAKEFIELD
COMM: 9-17-63
COMP: 9-21-63

LOCATION : SECTION 17-19S-39W
GREELEY COUNTY, KANSAS
CASING: 8 5/8" Set at 203'

Surface Soil	40
Sand and Clay	70
Shale	175
Blue Shale	207
Shale	880
Sand	925
Sand and Shale	1095
Shale	1500
Shale, Red Bed	2040
Red Beds and Shale	2210
Shells and Shale	2250
Shale	2350
Shale and Shells	2516
Anhydrite	2540
Anhydrite and Lime	2765
Shale and Shells	2920
Lime and Shale	2932
T.D.	2932

RECEIVED
STATE CORPORATION COMMISSION

OCT 28 1963

CONSERVATION DIVISION
Wichita, Kansas

STATE OF KANSAS)
) SS
COUNTY OF SEDGWICK)

I hereby certify that the above is a true and correct copy of the log on the SCHMIDT UNIT NO. 1 well, located in Section 17-19S-39W, Greeley County, Kansas.

EARL F. WAKEFIELD

By Fred A. Bales

Subscribed and sworn before me this 30th day of September, 1963.

My commission expires:
January 25, 1965

Wanda W. Riley
WANDA W. RILEY NOTARY

