

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-159-04436-00-00  
Spot: SWSENW Sec/Twnshp/Rge: 15-19S-10W  
2921 feet from S Section Line, 3616 feet from E Section Line  
Lease Name: FELDMAN Well #: 7  
County: RICE Total Vertical Depth: 3293 feet

Operator License No.: 33725  
Op Name: FOUNDATION ENERGY MANAGEMEN  
Address: 14800 LANDMARK BLVD STE 220  
DALLAS, TX 75254

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP	5.5	3206		
SURF	8	208		
PROD	5.5	3288		

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 09/29/2011 9:30 AM  
Plug Co. License No.: 32098 Plug Co. Name: CLASSIC WELL SERVICE, INC.  
Proposal Rcvd. from: KENT STRUBE Company: FOUNDATION ENERGY MGMT LL Phone: (620) 786-4161

Proposed Plugging Method: SEE BELOW. CP-1 INDICATES CASING LEAK BELOW 500'. THIS WELL HAD BEEN DENIED TA STATUS AND BEEN ALLOWED TO PRODUCE UNDER PACKER FOR AWHILE FOR OBSERVATION FOR ANY POTENTIAL.

Plugging Proposal Received By: B. J. HOPE Witness Type: PARTIAL  
Date/Time Plugging Completed: 10/10/2011 12:30 PM KCC Agent: VIRGIL CLOTHIER

Actual Plugging Report:

MIRU, CK BOTTOM. RUN TUBING TO 2800' AND PUMP 35 SX'S CEMENT. PULL TUBING OUT. LET SET FOR AWHILE AND TAG WITH WIRELINE AT 2583'. PERFORATE AT 1250', 900', AND 260'. CLASSIC WELL SERVICE, INC. ATTEMPTED TO RUN TUBING TO 1250', COULD NOT, SO CLASSIC WELL SERVICE RIGGED DOWN. ON 10-10-11 MIKE'S TESTING & SALVAGE, INC. #31529 CAME AND RAN TUBING--COULD ONLY GET TO 910', WORKING IT THRU TO THAT FOOTAGE AFTER BUMPING SOMETHING AT 265'. PUMPED 50 SX'S COMMON CEMENT AT 910'. SLOWLY PULLED TUBING TO 265', CATCHING ON COLLARS AS BEING PULLED OUT, AND CIRCUALTE CEMENT TO SURFACE OUT OF BOTH CASINGS. PULL TUBING OUT AND TOP OFF. USED APPROX. 240 SX'S TOTAL.

Perfs:

Top	Bot	Thru	Comments
2858	2866	CSG	

Remarks: 60-40 POZ, 4% GEL. COPELAND TICKET C-37311

Plugged through: TBG

District: 02

Signed

Virgil Clothier

(TECHNICIAN)

RECEIVED

OCT 24 2011

KCC WICHITA

Form CP-2/3

10/27/11

JK