

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-075-20856-00-00  
Spot: NESENWSE Sec/Twnshp/Rge: 6-26S-41W  
1770 feet from S Section Line, 1580 feet from E Section Line  
Lease Name: MELISSA ANN Well #: 1  
County: HAMILTON Total Vertical Depth: 6191 feet

Operator License No.: 34138  
Op Name: HONDO ENERGY PARTNERS, LLC  
Address: 5472 S. VENTURA CT.  
CENTENNIAL, CO 80015

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	1788		

Well Type: DH UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 10/04/2011 3:00 AM  
Plug Co. License No.: 33784 Plug Co. Name: TRINIDAD DRILLING LIMITED PARTNERSHIP  
Proposal Rcvd. from: JIM ROWLAND Company: HONDO ENERGY Phone: (303) 699-5920

Proposed Plugging Method: 1ST PLUG AT 1810' WITH 50 SX CMT. 2ND PLUG AT 650' WITH 50 SX CMT. 3RD PLUG AT 240' WITH 30 SX CMT. 4TH PLUG AT 60' WITH 20 SX CMT. 5TH PLUG TO CIRCULATE RAT HOLE WITH 30 SX CMT. 6TH PLUG TO CIRCULATE MOUSE HOLE WITH 20 SX CMT.

Plugging Proposal Received By: ERIC MACLAREN WitnessType: NONE  
Date/Time Plugging Completed: 10/04/2011 5:00 AM KCC Agent: ERIC MACLAREN

Actual Plugging Report:

Perfs:

1ST PLUG AT 1810' WITH 50 SX CMT. 2ND PLUG AT 650' WITH 50 SX CMT. 3RD PLUG AT 240' WITH 30 SX CMT. 4TH PLUG AT 60' WITH 20 SX CMT. 5TH PLUG TO CIRCULATE RAT HOLE WITH 30 SX CMT. 6TH PLUG TO CIRCULATE MOUSE HOLE WITH 20 SX CMT.

Remarks: USED 60/40 POZMIX 4% 1/4# FLO SEAL BY ALLIED.

Plugged through: DP

RECEIVED  
OCT 24 2011  
KCC WICHITA

District: 01

Signed Eric MacLaren  
(TECHNICIAN)

RECEIVED  
OCT 17 2011  
KCC DODGE CITY

Form CP-2/3  
10/27/11