

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-081-20571-00-02
Spot: SENWNW Sec/Twnshp/Rge: 6-30S-32W
4042 feet from S Section Line, 4123 feet from E Section Line
Lease Name: ORTH Well #: 2-6
County: HASKELL Total Vertical Depth: 5570 feet

Operator License No.: 33136
Op Name: ANADARKO E & P COMPANY LP
Address: PO BOX 1330
HOUSTON, TX 77251

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		2600		WITH 5 SX CMT
CIBP		2794		WITH 5 SX CMT
SURF	8.625	776		WITH 300 SX CMT
PROD	5.5	3292	0	WITH 675 SX CMT

Well Type: PI UIC Docket No: D27232.0 Date/Time to Plug: 09/30/2011 10:00 AM
Plug Co. License No.: 33338 Plug Co. Name: ORR ENTERPRISES, INC.
Proposal Rcvd. from: RONNIE ORR Company: ORR ENTERPRISES, INC. Phone: (580) 251-9618

Proposed Plugging Method: SET CIBP @ 2900' WITH 2 SX CMT. SET CIBP @ 2600' WITH 2 SX CMT. 25 SX CMT AT 1800'. CIRCULATE CMT FROM 800' TO SURFACE. FILL 5 1/2" X 8 5/8" CASING ANNULUS

Plugging Proposal Received By: JACK MACLASKEY WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 09/30/2011 4:30 PM KCC Agent: JACK MACLASKEY

Actual Plugging Report:

SET CIBP @ 2794' WITH 5 SX CMT. SET CIBP @ 2600' WITH 5 SX CMT. CIRCULATE HOLE WITH MUD & SPOTTED 30 SX CMT AT 1850' FILLED 5 1/2" CASING FROM 840' TO SURFACE. PUMPED 10 SX CMT INTO ANNULUS OF 5 1/2" X 8 5/8" CASING. PRESSURED TO 350 PSI.

Perfs:

Top	Bot	Thru	Comments
2970	2980		COUNCIL GROVE
2660	2780		CHASE

RECEIVED
OCT 24 2011
KCC WICHITA

Remarks: **COMPLIANCE ISSUE: NOV MIT LTR SENT** USED COMMON CEMENT BY ORR ENTERPRISES.

Plugged through: CSG

District: 01

RECEIVED
OCT 17 2011
KCC DODGE CITY

Signed Jack MacLaskey
(TECHNICIAN)

Form CP 2/3
10/27/11