

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-095-21726-00-00
Spot: NENWSW Sec/Twnshp/Rge: 7-28S-6W
2310 feet from S Section Line, 4290 feet from E Section Line
Lease Name: GREENLEAF RANCH Well #: 4
County: KINGMAN Total Vertical Depth: 3843 feet

Operator License No.: 5399
Op Name: AMERICAN ENERGIES CORPORATION
Address: 155 N MARKET STE 710
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	225		165 sx
PROD	4.5	3831	2950	100 sx

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 10/17/2011 12:00 AM
Plug Co. License No.: 31528 Plug Co. Name: MIKE KELSO OIL, INC.
Proposal Rcvd. from: JAMIE HARRIS Company: _____ Phone: _____

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: DAN FOX Witness Type: NONE
Date/Time Plugging Completed: 10/17/2011 5:00 PM KCC Agent: B. J. HOPE

Actual Plugging Report:

CUT PIPE OFF @ 2950'. SANDED BACK TO 3762' - CAPPED WITH 4 SX, 2700'
SPOTTED 35 SX CEMENT 2% CC, 1100' SPOTTED 35 SX CEMENT - TAGGED @980',
625' - 35 SX, 250' CIRCULATED TO SURFACE WITH 150 SX

Perfs:

Top	Bot	Thru	Comments
3831	3843		Mississippian

Remarks: COPELAND CEMENTING OUT OF GREAT BEND TICKET #37370 60/40/ 4%

Plugged through: CSG

District: 02

Signed

B. J. Hope

(TECHNICIAN)

RECEIVED

OCT 24 2011

Form CP-2/3

10/27/11

KCC WICHITA

✓