

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-113-20586-00-00
Spot: SWSWE Sec/Twnshp/Rge: 23-21S-2W
340 feet from S Section Line, 2322 feet from E Section Line
Lease Name: ORLANDO UNRUH Well #: B-3
County: MCPHERSON Total Vertical Depth: 3362 feet

Operator License No.: 5399
Op Name: AMERICAN ENERGIES CORPORATION
Address: 155 N MARKET STE 710
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	136		100 SX
PROD	4.5	3343	920	125 SX

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 09/28/2011 3:00 PM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: _____ Company: _____ Phone: _____

Proposed Plugging Method: AS PER KC RULES & REGS

Plugging Proposal Received By: JEFF KLOCK Witness Type: PARTIAL
Date/Time Plugging Completed: 09/30/2011 12:00 PM KCC Agent: SHANE JONES

Actual Plugging Report:
9/28/11 KELSO'S DROPPED SAND. 9/29/11 KELSO'S TAGGED SAND @ 3309' AND CAPPED W/4 SX. THEY SHUT DOWN DUE TO HIGH WINDS. 9/30/11 THEY RIPPED CASING @ 920'. THEY PULLED CASING TO 720' AND COPELAND TIED ON AND SPOTTED 35 SX PLUG. THEY THEN PULLED UP TO 415' AND COPELAND TIED AND PUMPED 195 SX. NO GOOD CIRCULATION OF CEMENT. COPELAND TK # USED 230 SX 60/40 POS W/4% GEL. 10/3/11 I CHECKED TOP PLUG, DOWN ABOUT 20'. I NOTIFIED AMERICAN ENERGIES. THEY WILL TOP OFF. 10/6/11 WELL CEMENTED TO SURFACE. OPERATOR WILL CUT OFF BELOW PLOW DEPTH AND FILL IN PIT.

Perfs:

Top	Bot	Thru	Comments
3343	3362	OH	

Remarks: KGS SHOWS LAST PRODUCTION WAS 2005 NO TA ON FILE
Plugged through: CSG

RECEIVED
OCT 25 2011
KCC WICHITA

District: 02

Signed [Signature]
(TECHNICIAN)

Form CP-2/3
10/27/11

JK