

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-135-23724-00-00
Spot: SENE Sec/Twnshp/Rge: 17-17S-24W
1955 feet from N Section Line, 640 feet from E Section Line
Lease Name: DICKMAN A Well #: 1
County: NESS Total Vertical Depth: 4422 feet

Operator License No.: 5086
Op Name: PINTAIL PETROLEUM, LTD.
Address: 225 N MARKET STE 300
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	256		WITH 160 SX CMT
DVT		1114		
PROD	5.5	4407	0	WITH 300 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 10/04/2011 10:30 AM
Plug Co. License No.: 31627 Plug Co. Name: WHITETAIL CRUDE, INC
Proposal Rcvd. from: BILLY BRINEY Company: WHITETAIL CRUDE Phone: (316) 785-5116

Proposed Plugging Method: RUN TBG TO BOTTOM & PUMP 35 SX CMT & 200# HULLS, THEN GEL SPACER TO 1800', THEN CMT TO SURFACE.

Plugging Proposal Received By: MICHAEL MAIER Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 10/04/2011 3:15 PM KCC Agent: MICHAEL MAIER

Actual Plugging Report:

RUN TBG TO 4396' & PUMPED 18 SX GELLED WATER FOLLOWED BY 35 SX CMT & 200# HULLS. PULLED TBG TO 1800' & CEMENTED WITH 160 SX CMT. CMT CIRCULATED. PULLED TBG & TOPPED OFF WITH 15 SX CMT. TIED ONTO BACKSIDE & PUMPED 30 SX CMT. PRESSURED TO 500# & HELD.

Perfs:

Top	Bot	Thru	Comments
4407	4422	OH	

Remarks: USED 60/40 POZMIX 4% GEL BY SWIFT SERVICES.

Plugged through: TBG

RECEIVED
OCT 26 2011
KCC WICHITA

District: 01

Signed Michael Maier
(TECHNICIAN)

RECEIVED
OCT 17 2011
KCC DODGE CITY

Form CP 275
10/27/11