

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-135-24480-00-01  
Spot: SWNESENE Sec/Twnshp/Rge: 34-16S-23W  
1827 feet from N Section Line, 419 feet from E Section Line  
Lease Name: SIDEBOTTOM OWWO Well #: 1-34  
County: NESS Total Vertical Depth: 4400 feet

Operator License No.: 5144  
Op Name: MULL DRILLING COMPANY, INC.  
Address: 1700 N WATERFRONT PKWY BLDG 12  
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	233		

Well Type: LH UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 10/12/2011 12:00 PM  
Plug Co. License No.: 33575 Plug Co. Name: WW DRILLING, LLC

Proposal Rcvd. from: \_\_\_\_\_ Company: \_\_\_\_\_ Phone: \_\_\_\_\_

Proposed Plugging Method: PLUG AT 690' WITH 80 SX CMT. PLUG AT 240' WITH 40 SX CMT. PLUG AT 60' WITH 20 SX CMT. CIRCULATE RAT HOLE WITH 30 SX CMT.

Plugging Proposal Received By: MICHAEL MAIER Witness Type: NONE  
Date/Time Plugging Completed: 10/12/2011 2:00 PM KCC Agent: MICHAEL MAIER

Actual Plugging Report:

Perfs:

**\*\*DRILL COLLAR & DRILL PIPE STUCK IN HOLE FROM 4400' TO 715'.\*\* 1ST PLUG FREE POINT DRILL PIPE. SHOT OFF AT 715'. PULL DRILL PIPE TO 690'. MIX & PUMP 80 SX CMT. 2ND PLUG PULL TO 240' & PUMP 40 SX CMT. 3RD PLUG PULL TO 60' & PUMP 20 SX CMT. 4TH PLUG TO CIRCULATE RAT HOLE WITH 30 SX CMT. NO MOUSE HOLE.**

Remarks: USED 60/40 POZMIX 4% GEL 1/4# FLO SEAL BY CONSOLIDATED.

Plugged through: DP

RECEIVED  
OCT 26 2011  
KCC WICHITA

District: 01

Signed

*Michael Maier*

(TECHNICIAN)

RECEIVED

OCT 18 2011

KCC DODGE CITY

Form OP-2/3

10/27/11