

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-159-04244-00-00  
Spot: SENENW Sec/Twnshp/Rge: 35-20S-6W  
4291 feet from S Section Line, 3074 feet from E Section Line  
Lease Name: HARDER A Well #: 3  
County: RICE Total Vertical Depth: 3393 feet

Operator License No.: 30525  
Op Name: LANGSTON, D. S.  
Address: 310 W CENTRAL STE 202  
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8	120		
MSCC		3381		
PROD	5.5	3378	1004	

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 10/11/2011 9:00 AM  
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.  
Proposal Rcvd. from: JAMIE HARRIS Company: MIKE'S TESTING & SALVAGE, INC. Phone: (620) 562-0895

Proposed Plugging Method: PER KCC REGULATIONS

Plugging Proposal Received By: SHANE JONES Witness Type: PARTIAL  
Date/Time Plugging Completed: 10/11/2011 11:30 AM KCC Agent: VIRGIL CLOTHIER

Actual Plugging Report:

MIRU, CK BOTTOM. SAND OPEN HOLE TO 3325' AND CAP WITH 5 SX'S CEMENT. CUT CASING OFF AT 1004' AND PULL TO 900' AND PUMP 35 SX'S COMMON CEMENT. PULL CASING TO 500'. LET SET AN HOUR AND TAG CEMENT AT 722'. PUMP 35 SX'S @ 500'. PULL CASING TO 250' AND CIRCUALTE CEMENT TO SURFACE. PULL CASING OUT AND TOP OFF.

Perfs:

Top	Bot	Thru	Comments
3378	3381	OH	

Remarks: DENIED TA-HFLD. COPELAND TICKET #C-37365. 60-40 POZ, 4% GEL, EXCEPT WHERE OTHERWISE NOTED.

Plugged through: CSG

District: 02

Signed Virgil Clothier  
(TECHNICIAN)

RECEIVED  
OCT 27 2011  
KCC WICHITA  
11/03/11

124