

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-015-21418-00-00  
Spot: NENWNW Sec/Twnshp/Rge: 14-26S-7E  
4856 feet from S Section Line, 4424 feet from E Section Line  
Lease Name: GRAY Well #: 1  
County: BUTLER Total Vertical Depth: 2773 feet

Operator License No.: 32702  
Op Name: KUTTER OIL, INC.  
Address: 701 E RIVER ST  
EUREKA, KS 67045

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	7.5	208		100 SX
PROD	4.5	2769	838	100 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 09/26/2011 8:00 AM  
Plug Co. License No.: 32701 Plug Co. Name: C & G DRILLING, INC.  
Proposal Rcvd. from: TOM GULICK Company: KUTTER OIL CO. Phone: (620) 583-4306

Proposed Plugging Method: SAND @ 2715 W/4 SKS, PULL PIPE, CIRC FROM 260' TO SURFACE 60/40 POZ MIX 4% GEL

Plugging Proposal Received By: STEVE VANGIESON Witness Type: PARTIAL  
Date/Time Plugging Completed: 09/30/2011 12:45 AM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

9/26/11 DUMPING SAND WELL BRIDGED OFF @ 426', RIH W/WORKSTRING CIRCULATING HOLE CLEAN @ 2790', CONSOLIDATED OIL WELL SERVICES ESTABLISHED CIRCULATION AND MIXED & PUMPED 25 SXS CLASS A COMMON 2% CC AND DISPLACED IN CASING. 9/27/11, FINISHED LAYING TBG DOWN. DUG OUT CELLER. REMOVED SLIPS FROM 4-1/2" CASING HEAD. SDON. 9/30/11, TAGGED CEMENT @ 2284'. CUT 4-1/2" CASING @ 838', LAYED DOWN 838' 4-1/2" CASING (25 JTS). RIH W/TBG @ 270', CONSOLIDATED OIL WELL SERVICES MIXED & PUMPED 65 SXS 60/40 POZ MIX 4% GEL TO SURFACE. CEMENT CIRCULATED. P&A COMPLETE 12:45 PM 9-30-2011 UNITED CEMENTING CEMENT TICKET #31618.

Perfs:

Top	Bot	Thru	Comments
2769	2773	OH	

Remarks: COMPLIANCE /TA

Plugged through: TBG

District: 02

Signed

  
(TECHNICIAN)

RECEIVED  
OCT 27 2011  
KCC WICHITA  
11/03/11  
Form CP-2/3

JK