

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-155-02837-00-00
Spot: SWNWNW Sec/Twnshp/Rge: 35-23S-4W
990 feet from N Section Line, 330 feet from W Section Line
Lease Name: GOERING Well #: 4-B
County: RENO Total Vertical Depth: 3591 feet

Operator License No.: 4252
Op Name: KAHAN AND ASSOCIATES, INC
Address: PO BOX 700780
TULSA, OK 74170

| String | Size | Depth (ft) | Pulled (ft) | Comments |
|--------|------|------------|-------------|----------|
| CIBP | | 2810 | | |
| SURF | 16 | 250 | | 250 SX |
| PROD | 7 | 3574 | | 500 SX |

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 05/26/2011 12:00 AM
Plug Co. License No.: 6819 Plug Co. Name: SCOTT'S WELL SERVICE INC
Proposal Rcvd. from: DAVID WILSON Company: _____ Phone: (918) 492-9797

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: STEVE VANGIESON Witness Type: PARTIAL
Date/Time Plugging Completed: 06/16/2011 2:00 PM KCC Agent: B. J. HOPE

Actual Plugging Report:

Perfs:

35 SX OF CEMENT @ 2713', ON 5/26/11. PERF CASING AT 535' RAISED CEMENT INSIDE 7 INCH TO SURFACE WITH 75 SX OF CEMENT. CUT HEAD OFF, NO CEMENT BETWEEN 7" AND 13". 6/14/11, RAN 1 INCH TO 280 FT BETWEEN 7 INCH AND 13 INCH CIRCULATED TO SURFACE WITH 160 SX, ALSO HAD CEMENT BETWEEN 13 INCH AND 16 INCH. CAME BACK ON THE 6/16/11 VERIFY CEMENT STAYED INSIDE PIPE.

Remarks: ALLIED CEMENTING OUT OF RUSSELL WAS USED FOR MOST OF CEMENT. DENIED TA JUNK IN HOLE AND 10 YEAR RULE.

Plugged through: TBG

District: 02

Signed

B. J. Hope

(TECHNICIAN)

RECEIVED
Form CP-2/3
OCT 27 2011 11/03/11
KCC WICHITA

JK