

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-057-20708-00-00  
Spot: SWSWSESE Sec/Twnshp/Rge: 27-25S-21W  
175 feet from S Section Line, 1100 feet from E Section Line  
Lease Name: BURKE Well #: 1-27  
County: FORD Total Vertical Depth: 4905 feet

Operator License No.: 4058  
Op Name: AMERICAN WARRIOR, INC.  
Address: 3118 CUMMINGS RD PO BOX 399  
GARDEN CITY, KS 67846

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	287		WITH 165 SX CMT
PC		1359		CMT TO SURFACE
PROD	5.5	4880	0	WITH 125 SX CMT

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 10/20/2011 1:30 PM  
Plug Co. License No.: 32382 Plug Co. Name: SWIFT SERVICES, INC.  
Proposal Rcvd. from: JODY SMITH Company: AMERICAN WARRIOR Phone: (620) 275-2963

Proposed Plugging Method: RUN TBG TO 4750' & SPOT 200# HULLS & 30 SX CMT. PULL TBG TO 1450' & LOAD HOLE. CIRCULATE CMT FROM 1450' TO 0'. TOOH & TOP OFF. CHECK ANNULUS.

Plugging Proposal Received By: KEN JEHLIK Witness Type: NONE  
Date/Time Plugging Completed: 10/20/2011 10:30 AM KCC Agent: KEN JEHLIK

Actual Plugging Report:

1ST PLUG RIHWT TO 4750' & PUMP 200# HULLS & 30 SX CMT. 2ND PLUG PULL TBG TO 1450'. CIRCULATE CMT TO SURFACE WITH 155 SX CMT. TOP OFF CASING WITH 30 SX CMT. 3RD PLUG PRESSURED ANNULUS TO 500#.

Perfs:


Top	Bot	Thru	Comments
4828	4829		
4802	4812		

Remarks: USED 60/40 POZMIX 4% GEL BY SWIFT SERVICES.

Plugged through: TBG

District: 01

Signed



(TECHNICIAN)

RECEIVED

OCT 21 2011

KCC DODGE CITY

RECEIVED

OCT 28 2011

KCC WICHITA

Form CP27

10/02/11