

TO:
STATE CORPORATION COMMISSIO
CONSERVATION DIVISION - PLUGGIN
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 6720

API Well Number: 15-049-21943-00-00
Spot: SWNESESE Sec/Twnshp/Rge: 25-30S-10E
885 feet from S Section Line, 341 feet from E Section Line
Lease Name: STEPHENS Well #: 1
County: ELK Total Vertical Depth: 1900 feet

Operator License No.: 4448
Op Name: PERKINS OIL ENTERPRISES, INC.
Address: PO BOX 707
HOWARD, KS 67349

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 10/20/2011 11:00 AM
Plug Co. License No.: 34203 Plug Co. Name: PIRATE WELL SERVICE, LLC
Proposal Rcvd. from: J.R. PERKINS Company: _____ Phone: (620) 374-2133

Proposed Plugging Method: TD IS APPROX. 1900' & IS PERF IN THE MISSISSIPPI. PERF WELL 1670' & @ 350'. RUN TUBING TO BOTTOM & PUMP GEL & PUMP 10 SX CEMENT. PULL TUBING TO 1670' & PUMP 10 SX CEMENT, PULL TUBING TO 350' PUMP CEMENT TO SURFACE. PULL REST OF TUBING & TOP OFF WELL.

Plugging Proposal Received By: DUANE SIMS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed 10/20/2011 11:30 AM KCC Agent: DUANE SIMS

Actual Plugging Report:

Perfs:

Ran 2" to 1829' gelled hole and spotted 10 sack plug. Pulled up to 1670' and spotted 5 sack plug. Pulled up to 429' and circulated cement to surface. Pulled 2" and topped well off. A total of 55 sacks of cement were used to plug this well.

RECEIVED

OCT 20 2011 DAS

KCC Chanute Dist. #3

Remarks:

Plugged through: TBG

District: 03

Signed



(TECHNICIAN)

RECEIVED

Form CP-2/3

OCT 28 2011

11/03/11

KCC WICHITA