

TO:  
STATE CORPORATION COMMISSIO  
CONSERVATION DIVISION - PLUGGIN  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 6720

API Well Number: 15-049-19265-00-00  
Spot: NENWSESW Sec/Twnshp/Rge: 30-30S-11E  
1004 feet from S Section Line, 3597 feet from E Section Line  
Lease Name: PICKELL Well #: 7  
County: ELK Total Vertical Depth: 2277 feet

Operator License No.: 4448  
Op Name: PERKINS OIL ENTERPRISES, INC.  
Address: PO BOX 707  
HOWARD, KS 67349

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		1617		
CIBP		1995		
PROD	5.5	2273		

Well Type: OIL UIC Docket No: UIC Docket No: Date/Time to Plug: 10/21/2011 10:00 AM  
Plug Co. License No.: 34203 Plug Co. Name: PIRATE WELL SERVICE, LLC  
Proposal Rcvd. from: J R PERKINS Company: Phone: (620) 374-2133

Proposed Plugging Method: PERF WELL AT 1200' AND 350' RUN TUBING TO 1617 PUMP GEL AND PUMP 10 SX CMENT PULL TUBING TO 1200 PUMP 10 SACKS CMT AND PULL TUBING TO 350 PUMP CEMENT TO SURFACE PULL REST OF TUBING AND TOP OFF

Plugging Proposal Received By: DUANE SIMS WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed 10/21/2011 12:00 PM KCC Agent: DUANE SIMS

Actual Plugging Report:

Perforated at 1200' and 350'. Ran 2" to 1340' gelled hole and spotted 12 sack plug. Pulled up to 1200' and spotted 7 sack plug. Pulled up to 350 and circulated cement to surface. Pulled 2" and topped well off. A total of 60 sacks of cement were used to plug this well.

Perfs:

Top	Bot	Thru	Comments
2273	2287		ARBUCKLE
1589	1601		OSWEGO

RECEIVED

OCT 21 2011 DAS


KCC Chanute Dist. #3

Remarks:

Plugged through: TBG

District: 03

Signed



(TECHNICIAN)

RECEIVED  
OCT 28 2011  
KCC WICHITA

Form CP-2/3

10/03/11