

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-053-20422-00-00
Spot: SWSWSW Sec/Twnshp/Rge: 21-17S-10W
320 feet from S Section Line, 5004 feet from E Section Line
Lease Name: SCHEPMANN Well #: 1
County: ELLSWORTH Total Vertical Depth: 3330 feet

Operator License No.: 33186
Op Name: LB EXPLORATION, INC.
Address: 2135 2ND RD
HOLYROOD, KS 67450

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	269		175 SXS CMT
PROD	4.5	3312		100 SXS

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 08/29/2011 11:30 AM
Plug Co. License No.: 6901 Plug Co. Name: D S & W WELL SERVICING, INC.
Proposal Rcvd. from: TIM DICKSON Company: D.S.&W WELL SERVICING Phone: (620) 562-4258

Proposed Plugging Method: SEE BELOW. CP-1 INDICATES POOR WELL CONDITION

Plugging Proposal Received By: PATRICK SHIELDS Witness Type: PARTIAL
Date/Time Plugging Completed: 08/30/2011 3:00 PM KCC Agent: VIRGIL CLÓTHIER

Actual Plugging Report:

MIRU, ENCOUNTERED BRIDGE AT 688'. RUN TUBING ON THRU BRIDGE TO 3267' AND PUMP 50 SX'S COMMON CEMENT WITH 2% CC. PULL TUBING ON OUT--LET SET OVERNIGHT. COME BACK MORNING OF 8-30-11 AND TAG CEMENT AT 2950'. PERFORATE AT 1325', 1000', AND 325'. RUN TUBING TO 1325' AND PUMP 35 SX'S CEMENT WITH 2% CC. LET SET FOR 1-1.5 HRS. AND TAG AT 1285'. PULL TUBING TO 1000' AND PUMP 35 SX'S CEMENT. PULL TUBING TO 325' AND CIRCULATE CEMENT TO SURFACE. CONNECT ON TO SURFACE CASING AND PUMP CEMENT--PRESSURED UP TO 350#S, SHUT IN. PULL TUBING OUT AND TOP OFF. RE-CK'D ON 10-10-11, OPERATOR HAD GOTTEN BACK IN PREVIOUS WEEK AND TOPPED OFF WITH SLURRY MIX. ELLSWORTH REDI-MIX TICKET #44163.

Perfs:

Top	Bot	Thru	Comments
3312	3330	OH	

Remarks: ALLIED CEMENT #37355. DENIED TA WELL--HIGH FLUID LEVEL.

Plugged through: TBG

District: 02

Signed Virgil Clothier
(TECHNICIAN)

RECEIVED 10/24/11
Form CP-2/3
OCT 17 2011
KCC WICHITA