

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-053-20462-00-00
Spot: SENESW Sec/Twnshp/Rge: 21-17S-10W
1645 feet from S Section Line, 3098 feet from E Section Line
Lease Name: SCHEPMANN Well #: 3
County: ELLSWORTH Total Vertical Depth: 3335 feet

Operator License No.: 33186
Op Name: LB EXPLORATION, INC.
Address: 2135 2ND RD
HOLYROOD, KS 67450

| String | Size | Depth (ft) | Pulled (ft) | Comments |
|--------|-------|------------|-------------|-------------|
| CIBP | 4.5 | 3270 | | |
| SURF | 8.625 | 280 | | 175 SXS |
| PROD | 4.5 | 3323 | | 100 SXS CMT |

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 08/26/2011 10:30 AM
Plug Co. License No.: 6901 Plug Co. Name: D S & W WELL SERVICING, INC.
Proposal Rcvd. from: TIM DICKSON Company: D.S.&W WELL SERVICING Phone: (620) 786-4258

Proposed Plugging Method: SEE BELOW. CP-1 INDICATED WELL AS POOR CONDITION.

Plugging Proposal Received By: PATRICK SHIELDS Witness Type: PARTIAL
Date/Time Plugging Completed: 08/26/2011 2:30 PM KCC Agent: VIRGIL CLOTHIER

Actual Plugging Report:

MIRU, CK BOTTOM. SET CIBP @3270' AND CAP WITH 2 SX'S CEMENT. PERFORATE AT 1325', 1000', AND 325'. RUN TUBING TO 1325' AND PUMP 35 SX'S CEMENT WITH CC. PULL TUBING UP SOME AND LET SET. TAG CEMENT WITH TUBING AFTER 1.5 HRS AT 1235'. PULL TUBING UP TO 1000' AND PUMP 35 SX'S CEMENT. PULL TUBING UP TO 325' AND CIRCULATE TO SURFACE. PULL TUBING OUT AND TOP OFF. CONNECTED ONTO SURFACE CASING AND PUMPED CEMENT--PRESSURED UP TO 300#'S AND STOPPED. TOP OFF CASING AGAIN. USED 250 SX'S: RE-CK'D ON 10-10-11, OPERATOR HAD GOTTEN BACK IN THE PREVIOUS WEEK TO TOP OFF WELL WITH SLURRY MIX. ELLSWORTH REDI-MIX TICKET #44163.

Perfs:

| Top | Bot | Thru | Comments |
|------|------|------|----------|
| 3323 | 3335 | OH | |

Remarks: 60-40 POZ, 4% GEL. PERF TECH #6691. ALLIED TICKET #37268. DENIED TA WELL--HIGH FLUID WELL.

Plugged through: TBG

District: 02

Signed

Virgil Clothier
(TECHNICIAN)

10/24/11
RECEIVED
Form CP-2/3

OCT 17 2011

KCC WICHITA