

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-007-22976-00-00
Spot: N2SENE Sec/Twnshp/Rge: 7-30S-11W
1650 feet from N Section Line, 660 feet from E Section Line
Lease Name: FISCHER Well #: 1-7
County: BARBER Total Vertical Depth: 3875 feet

Operator License No.: 32192
Op Name: PRIDE ENERGY COMPANY, A GENERA
Address: P O BOX 701950
TULSA, OK 74170

| String | Size | Depth (ft) | Pulled (ft) | Comment |
|--------|-------|------------|-------------|-----------------|
| CIBP | | 2570 | | WITH 2 SX CMT |
| CIBP | | 3100 | | |
| CIBP | | 3600 | | |
| SURF | 8.625 | 313 | | WITH 250 SX CMT |
| DVT | | 2500 | | 310 SX CMT. |
| PROD | 5.5 | 3850 | 694 | WITH 250 SX CMT |
| RBP | | 2818 | | |

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 09/29/2011 12:00 PM
Plug Co. License No.: 34082 Plug Co. Name: ALLIANCE WELL SERVICE INC.
Proposal Rcvd. from: BARRY WALTERS Company: ALLIANCE WELL SERVICE INC. Phone: (620) 672-9100

Proposed Plugging Method: SET CIBP @ 2700' & PUT 2 SX CMT ON TOP OF CIBP. PLUG AT 700' WITH 10 SX GEL & 50 SX CMT. PLUG AT 350' WITH 50 SX CMT. PLUG AT 40' WITH 20 SX CMT.

Plugging Proposal Received By: RICHARD LACEY WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 09/29/2011 1:15 PM KCC Agent: STEVE PFEIFER

Actual Plugging Report:

SET CIBP @ 2570' & PUT 2 SX CMT ON TOP OF CIBP. 1ST PLUG AT 695' WITH 10 SX GEL & 50 SX CMT. 2ND PLUG AT 340' WITH 50 SX CMT. 3RD PLUG AT 60' WITH 20 SX CMT.

Perfs:

| Top | Bot | Thru | Comments |
|------|------|------|-------------|
| 3739 | 3744 | | TORONTO |
| 3359 | 3367 | | TOPEKA |
| 3340 | 3344 | | TOPEKA |
| 3181 | 3186 | | TOPEKA |
| 2946 | 2952 | | TARKIO |
| 2752 | 2782 | | INDIAN CAVE |

Remarks: USED 60/40 POZMIX 4% GEL BY BASIC ENERGY.

Plugged through: TBG

District: 01

RECEIVED
OCT 17 2011
KCC DODGE CITY

Signed

Stephen J. Pfeifer
(TECHNICIAN)

RECEIVED
OCT 19 2011
KCC WICHITA
10/24/11