

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-007-19042-00-00
Spot: NWSWSENE Sec/Twnshp/Rge: 4-33S-11W
2970 feet from S Section Line, 990 feet from E Section Line
Lease Name: INSLEE Well #: 1
County: BARBER Total Vertical Depth: 4455 feet

Operator License No.: 3273
Op Name: HERMAN L. LOEB, LLC
Address: PO BOX 838
LAWRENCEVILLE, IL 62439

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		4360		WITH 2 SX CMT
SURF	8.625	280		WITH 200 SX CMT
PROD	0.5	4455	2600	

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 10/03/2011 8:00 AM
Plug Co. License No.: 5105 Plug Co. Name: CLARKE CORPORATION
Proposal Rcvd. from: MARK MORGENSTERN Company: CLARKE CORPORATION Phone: (620) 886-5665

Proposed Plugging Method: CIBP @ 4360' WITH 2 SX CMT. PLUG AT 600' WITH 10 SX GEL & 50 SX CMT. PLUG AT 310' WITH 50 SX CMT. PLUG AT 60' WITH 20 SX CMT.

Plugging Proposal Received By: STEVE PFEIFER Witness Type: NONE
Date/Time Plugging Completed: 10/03/2011 10:40 AM KCC Agent: STEVE PFEIFER

Actual Plugging Report:

CIBP @ 4360' WITH 2 SX CMT. 1ST PLUG RUN TBG TO 600' & PUMP 10 SX GEL & 50 SX CMT. 2ND PLUG AT 310' WITH 50 SX CMT. 3RD PLUG AT 60' WITH 20 SX CMT.

Perfs:


Top	Bot	Thru	Comments
4418	4450		MISSISSIPPIAN

Remarks: USED 60/40 POZMIX 4% GEL BY QUALITY WELL CEMENTING.

Plugged through: TBG

District: 01

Signed


(TECHNICIAN)

RECEIVED
OCT 17 2011
KCC DODGE CITY

10/24/11
RECEIVED
OCT 19 2011
KCC WICHITA