

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-195-22353-00-00
Spot: N2N2SW Sec/Twnshp/Rge: 11-15S-22W
2230 feet from S Section Line, 1240 feet from W Section Line
Lease Name: SCHMIDT PR Well #: 1-11
County: TREGO Total Vertical Depth: 4280 feet

Operator License No.: 5086
Op Name: PINTAIL PETROLEUM, LTD.
Address: 225 N MARKET STE 300
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	217	0	150 SX CMT.
T1	2.375	4149		
PC		1710		
PROD	5.5	4279	0	200 SX CMT.

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 10/07/2011 10:00 AM
Plug Co. License No.: 31627 Plug Co. Name: WHITETAIL CRUDE, INC
Proposal Rcvd. from: BILLY BRINEY Company: WHITETAIL CRUDE, INC Phone: (785) 798-3641

Proposed Plugging Method: Ordered 270 sxs 60/40 pozmix - 4% gel - 250# hulls - 20 sxs gel.
PC at 1710' with 125 sxs cement.

Plugging Proposal Received By: MARVIN MILLS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 10/07/2011 1:45 PM KCC Agent: MARVIN MILLS

Actual Plugging Report:

Ran tubing to 4079' - pumped 18 sxs gel - followed with 50 sxs cement.
Pulled tubing to 2000' - pumped 260 sxs cement - good circulation of cement.
Pulled tubing - topped off with 15 sxs cement - full.
Tied onto backside and pumped 17 sxs cement.
S.I.P. 300#.

Perfs:


Top	Bot	Thru	Comments
4194	4198		CHEROKEE SAND
4192	4200		CHEROKEE SAND
4135	4138		CHEROKEE SAND

Remarks: SWIFT CEMENTING COMPANY-TICKET #22369.

Plugged through: TBG

RECEIVED
OCT 20 2011
KCC WICHITA

District: 04

Signed 
(TECHNICIAN)

CM

Form CP-2/3

10/24/11

OCT 07 2011