

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-205-19911-00-01  
Spot: SESWNWNE Sec/Twnshp/Rge: 29-30S-16E  
1070 feet from N Section Line, 2300 feet from E Section Line  
Lease Name: UNIT 1 - MONG Well #: 22K  
County: WILSON Total Vertical Depth: 860 feet

Operator License No.: 3830  
Op Name: A X & P, INC.  
Address: PO BOX 1176  
INDEPENDENCE, KS 67301

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	4.875	751		20 SX
COND	12	40		6 SX
PROD	2	800		9 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 12/21/2010 8:00 AM  
Plug Co. License No.: 5491 Plug Co. Name: W & W PRODUCTION COMPANY, GENERAL PARTNERSHIP  
Proposal Rcvd. from: J.J. HANKE Company: A X & P, INC Phone: (620) 325-5212

Proposed Plugging Method: VERIFY CEMENT TOP BY RUNNIGN BOND LOG INSIDE 2". PERFORATE ABOVE CEMENT AND @ 200'. SQUEEZE CEMENT TO SURFACE. NOTE OLD MIT (ATTACHED).

Plugging Proposal Received By: ALAN DUNNING Witness Type: NONE  
Date/Time Plugging Completed: 12/21/2010 5:00 PM KCC Agent: ALAN DUNNING

Actual Plugging Report:

Perfs:

The well was perforated at 678' and 200'. The well was then pumped full of cement thru the 2" production pipe with good circulation. The operator reported that 293 sacks of portland cement were used to plug well.

RECEIVED  
OCT 18 2011 AD  
KCC Chanute Dist. #3

RECEIVED  
OCT 20 2011  
KCC WICHITA

Remarks:

Plugged through: CSG

District: 03

Signed Alan Dunning  
(TECHNICIAN)

10/24/11  
Form CP-2/3