

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-205-19908-00-00
Spot: NWSWNWNE Sec/Twnshp/Rge: 29-30S-16E
974 feet from N Section Line, 2573 feet from E Section Line
Lease Name: UNIT 1 - MONG Well #: 28
County: WILSON Total Vertical Depth: 820 feet

Operator License No.: 3830
Op Name: A X & P, INC.
Address: PO BOX 1176
INDEPENDENCE, KS 67301

String	Size	Depth (ft)	Pulled (ft)	Comments
COND	12	40	0	UNKNOWN
PROD	4.875	754	0	
PROD	2	780	0	9 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 12/21/2010 8:00 AM
Plug Co. License No.: 5491 Plug Co. Name: W & W PRODUCTION COMPANY, GENERAL PARTNERSHIP
Proposal Rcvd. from: J.J. HANKE Company: A X & P, INC. Phone: (620) 325-5212

Proposed Plugging Method: VERIFY CEMENT TOP BY RUNNING BOND LOG INSIDE 2". PERFORATE ABOVE CEMENT AND @ 200'. SQUEEZE CEMENT TO SURFACE.

Plugging Proposal Received By: ALAN DUNNING Witness Type: NONE
Date/Time Plugging Completed: 12/21/2010 5:00 PM KCC Agent: ALAN DUNNING

Actual Plugging Report:

The well was perforated at 650', 200' and 55'. A 1" cement string was run to 800' inside the 2" production pipe. The well was then pumped full of cement from btm to top thru this cement string. The operator reported that 124 sacks of portland cement were used to plug well.

Perfs:

RECEIVED

OCT 17 2011

AD

KCC Chanute Dist. #3

RECEIVED

OCT 20 2011

KCC WICHITA

Remarks:

Plugged through: CSG

District: 03

Signed

Alan Dunning
(TECHNICIAN)

10/24/11
Form CP-2/3