

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-163-30151-00-01  
Spot: NWNESW Sec/Twnshp/Rge: 7-10S-20W  
2310 feet from S Section Line, 3630 feet from E Section Line  
Lease Name: TEMPLE Well #: #2  
County: ROOKS Total Vertical Depth: 3316 feet

Operator License No.: 33937  
Op Name: NEAL LAFON REALTY INC. DBA MERI  
Address: 1475 WARD DR  
FRANKTOWN, CO 80116

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	174	0	w/unknown sxs cmt
PROD	5.5	3312	0	w/unknown sxs cmt

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 10/12/2011 10:30 AM  
Plug Co. License No.: 4072 Plug Co. Name: PLAINS, INC  
Proposal Revd. from: NEAL LAFON Company: MERIDIAN ENERGY INC. Phone: (303) 688-4022

Proposed Plugging Method: Ordered 250 sxs 60/40 pozmix - 4% gel with 1/4# flocele per sack - 500# hulls.  
Casing leaks.

Plugging Proposal Received By: CASE MORRIS Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 10/12/2011 1:30 PM KCC Agent: PAT STAAB

Actual Plugging Report:

Perfs:  
RIH with tubing to 3312' - Consolidated rigged to tubing and pumped 25 sxs 60/40 pozmix - 4% gel.  
Pulled tubing to 1770' - Consolidated rigged to tubing and pumped 40 sxs cement with 50# hulls mixed in.  
Pulled tubing to 1050' - Consolidated rigged to tubing and pumped 100 sxs cement with 200# hulls mixed in.  
Pulled tubing to 60' - Consolidated rigged to tubing and pumped 25 sxs cement to circulate cement to surface.  
Pulled tubing - hole standing full.

Remarks: CONSOLIDATED CEMENTING COMPANY-TICKET #33635.

Plugged through: TBG

District: 04

Signed \_\_\_\_\_

(TECHNICIAN)

RECEIVED

10/24/11  
Form CP-2/3

OCT 21 2011

KCC WICHITA

OCT 18 2011