

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-051-02736-00-00
Spot: N2N2NW Sec/Twnshp/Rge: 22-13S-17W
4950 feet from S Section Line, 3960 feet from E Section Line
Lease Name: DREILING Well #: 5
County: ELLIS Total Vertical Depth: 3596 feet

Operator License No.: 32169
Op Name: DOPITA, DON DBA MAVERICK OIL CO.
Address: 107 W ANN ST
ZURICH, KS 67663

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	240	0	200 SX
PROD	5.5	3580	0	325 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 10/13/2011 12:00 PM
Plug Co. License No.: 34519 Plug Co. Name: DOUBLE DRUM WELL SERVICE LLC
Proposal Rcvd. from: DON DOPITA Company: MAVERICK OIL CO. Phone: (785) 650-4954

Proposed Plugging Method: Ordered out 450 sxs 60/40 pozmix - 4% gel - 500# hulls.
Casing leaks 334' - 634'.
No records of upper pipe protection.

Plugging Proposal Received By: PAT STAAB Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 10/13/2011 4:45 PM KCC Agent: RICHARD WILLIAMS

Actual Plugging Report:

Perforated two holes at 1650' and 1250'.
Ran tubing to 3460'. Quality Oil Well Cementing pumped 100 sxs cement with 300# hulls.
Pulled to 2400' - pumped 75 sxs cement with 100# hulls.
Pulled to 1650' - pumped 100 sxs cement with 100# hulls.
Pulled to 900' - pumped 60 sxs - circulated with cement.
PTOH. Topped 5 1/2" casing off with 20 sxs cement - casing full.
Hooked up to backside. Instant pressure. Blew hole in 8 5/8" below head.

Perfs:

Top	Bot	Thru	Comments
3584	3596		OPEN HOLE
3476	3480		
3470	3473		

Remarks: QUALITY OIL WELL CEMENTING-TICKET #5192.

Plugged through: TBG

District: 04

Signed _____

Richard Williams
(TECHNICIAN)

RECEIVED

OCT 21 2011

KCC WICHITA

OCT 19 2011

cm
10/24/11
Form CP-2/3