

1  
to:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 151-21,730 0000  
15' East of  
C E/2 SW, SEC. 2, T 27 S, R 13 W/E  
1320 feet from S section line  
3285 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5435  
Operator: Bowers Drilling Co., Inc.  
Name & Address  
125 North Market  
Wichita, KS 67202

Lease Name Briggeman Well # 3-A  
County Pratt  
Well Total Depth 4410 Arbuckle 43.33 feet  
Conductor Pipe: Size feet  
Surface Casing: Size 8 5/8 feet 967

Abandoned Oil Well Gas Well Input Well SWD Well D&A X

Other well as hereinafter indicated

Plugging Contractor Red Tiger Drilling Co. License Number 5302  
Address 1720 Kansas State Bank Building, Wichita, KS 67202

Company to plug at: Hour: 11:30 pm Day: 28 Month: October Year: 19 85

Plugging proposal received from Bruce Fickle

(company name) Red Tiger (phone) 316-263-2371

were: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 1200' Elevation 1923

- 1st plug 50' into the Arbuckle if necessary with 50 sx cement
- 2nd plug at the base of the Anhydrite with 50 sx cement
- 3rd plug 30' below the base of the surface pipe with 50 sx cement solid bridge
- 4th plug hulls - plug at 40' -- cement to surface with 10 sx cement
- 6th plug to circulate rat hole with 15 sx cement

Plugging Proposal Received by Paul A. Luthi (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None X

Operations Completed: Hour: 1:45 am Day: 29 Month: October Year: 19 85

ACTUAL PLUGGING REPORT 1st plug at 4365' with 50 sx cement, 2nd plug at 1236' with 50 sx cement, 3rd plug at 1000' with 50 sx cement, 4th & 5th plugs - solid bridge - hulls - plug at 40' -- cement to surface with 10 sx cement, 6th plug to circulate rat hole with 15 sx cement

Remarks: Used 60/40 Pozmix 6% gel by BJ-Titan  
(If additional description is necessary, use BACK of this form.)

RECEIVED

NOV 4 1985

NOV 1 1985

Signed Paul A. Luthi (TECHNICIAN)

DATE 10873 10-29

CONSERVATION DIVISION  
Wichita, Kansas