

To: 1
STATE CORPORATION COMMISSION
Wichita State Office Bldg. PLUGGING SECTION
130 S. Market, Room 2078
Wichita, KS 67202

API NUMBER 15- 055-21,486 0000 158
5' S of
SE SE NE, SEC. 24, T. 23 S, R. 34 W/E

TECHNICIAN'S PLUGGING REPORT

Operator License # 31593
Operator: Westport Oil & Gas Co., Inc.
Name & Address 410 17th St., #2410
Denver, CO 80202

2315 feet from ~~NX~~ section line
330 feet from E section line

Lease Name Garden City Well # 42-24
County Finney
Well Total Depth 4750 154.37 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 1655

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X
Other well as hereinafter indicated _____

Plugging Contractor Abercrombie RTD, Inc. License Number 30684
Address 150 N. Main, Ste. 801, Wichita, KS 67202

Company to plug at: Hour: 5 p.m. Day: 18 Month: 3 Year: 19 96

Plugging proposal received from Walter Brown
(company name) Abercrombie RTD, Inc. (phone) 316-262-1841

Work: to fill hole with heavy mud and spot cement through drill pipe
1st plug at Hugoton/Council Grove with 100 sx cement,
2nd plug at 1690' with 50 sx cement, 3rd plug at 800' with 40 sx cement,
4th plug at 40' with 10 sx cement,
5th plug to circulate rathole with 15 sx cement.

Plugging Proposal Received by Richard Lacey
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None X
Operations Completed: Hour: 10 p.m. Day: 18 Month: 3 Year: 19 96

ACTUAL PLUGGING REPORT 1st plug at 3140' with 100 sx cement,
2nd plug at 1690' with 50 sx cement,
3rd plug at 800' with 40 sx cement,
4th plug at 40' with 10 sx cement,
5th plug to circulate rathole with 15 sx cement.

RECEIVED
KANSAS CORPORATION COMMISSION

MAR 22 1996
03-22-96

CONSERVATION DIVISION
WICHITA, KS

Remarks: Used 60/40 Pozmix 6% gel by Allied.
(If additional description is necessary, use BACK of this form.)

INNOVATED
I (did not) observe this plugging.

Signed Richard M. Lacey
(TECHNICIAN)

DATE 3-18-96
WV. NO. 45197

EFFECTIVE DATE: 3-9-96

State of Kansas

055-21,486

DISTRICT # 1

NOTICE OF INTENTION TO DRILL

SEA? Yes No

Must be approved by the K.C.C. five (5) days prior to commencing well

Expected Spud Date 03 07 96 month day year

Spot S SOUTH OF SE SE NE Sec 24 Twp 23 S. Rg 34 East West

OPERATOR: License # 31593 Name: WESTPORT OIL & GAS CO., INC. Address: 410 Seventeenth Street #2410 City/State/Zip: Denver, Colorado 80202 Contact Person: Jim Myers Phone: (303) 573-5404

2315 feet from North line of Section 330 feet from East line of Section IS SECTION X REGULAR (NOTE: Locate well on the Section Plat on Reverse Side; County: Finney Lease Name: Garden City Well #: 42-24 Field Name: NE Pott

CONTRACTOR: License #: 30684 Name: ABERCROMBIE DRILLING

*Is this a Prorated/Spaced Field? yes X no Target Formation(s): Mississippian Nearest Lease or unit boundary: 330' Ground Surface Elevation: 2902 feet MSL Water well within one-quarter mile: yes X no Public water supply well within one mile: yes X no Depth to bottom of fresh water: 320 Depth to bottom of usable water: 1060 Surface Pipe by Alternate: X 1 2 Length of Surface Pipe Planned to be set: 1600 Length of Conductor pipe required: Projected Total Depth: 4800 Formation at Total Depth: Mississippian Water Source for Drilling Operations: X well far pond other

Well Drilled For: Well Class: Type Equipment:

- X Oil ... Enh Rec ... Infield X Mud Rotary ... Gas ... Storage ... Pool Ext. ... Air Rotary ... OWD ... Disposal ... Wildcat ... Cable ... Seismic; ... # of Holes X Other

If OWD: old well information as follows: Operator: Well Name: Comp. Date: Old Total Depth

Directional, Deviated or Horizontal wellbore? yes X no If yes, true vertical depth: Bottom Hole Location: Exp. 9/4/96

DWR Permit #: AFFL. OF FROM DWR Will Cores Be Taken? yes X no If yes, proposed zone: 1080' Alt. I Req.

KANSAS CORPORATION COMMISSION MAR 22 1996

AFFIDAVIT

The undersigned hereby affirms that the drilling, completion and eventual plugging of this well will comply with K.S.A. 55-

* PRORATED AND SPACED IN CHASE AND COUNCIL GROVE

CONSERVATION DIVISION HUTCHIN, KS

Pusher Walter Brown SPUD DATE 3-9-96 INIT. R.L

LENGTH SURFACE PLANNED 1600 ± 1450 RESERVE PIT STATUS- REMOVE FLUID LINED after salt sect. bbls. when done bbls.

RATHOLED AHEAD? Y N SIZE HOLE SURFACE PIPE 8 3/4 @ 7655 CONDUCTOR ANHYDRITE T- B- ELEVATION

Table with columns: TP, FORMATION, RAR PIPE @, DV TOOL, ALT II DONG, FT. W/, SX, Y, N, Ar buckle Plug @, Ft. W/, SX, Bug./Council @, Ft. W/, SX, Anhydrite Base @, Ft. W/, SX, 1/2 Base Anyh. @, Ft. W/, SX, 1/2, 1/2 Plug @, Ft. W/, SX, Bottom Surface @, Ft. W/, SX, 40' Plug @, Ft. W/, SX

RAT HOLE CIRC/W 15 SX MOUSE HOLE W/ SX WATER WELL SX (Irr. Well Pond Hauling) TECHNICIAN AL DATE 3-15-96

TYPE OF CEMENT 60/40 per 6/10/91 STARTING TIME 5: (AM/PM) DATE 3-18 COMPLETION TIME 10: (AM/PM) DATE 3-18 CEMENT COMPANY Allco