

15-053-19131-0000  
2-040611 280  
P

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - Plugging Section  
200 Colorado Derby Building  
Wichita, Kansas 67202

API NUMBER: 9/63 - SWD, no docket #

SE SW NW, SECTION 25 TOWNSHIP 16 RANGE 9W

OPERATOR LICENSE # 8653 3300 FEET FROM S SECTION LINE  
4920 FEET FROM E SECTION LINE

OPERATOR Petroleum Technologies, Inc.  
NAME & 500 Nichols Road, #407  
ADDRESS Kansas City, MO 64112

LEASE NAME: Gregory "A" #2  
COUNTY: Ellsworth  
WELL TOTAL DEPTH: 3460' 112.45

CONDUCTOR PIPE: " @ '  
SURFACE CASING: 8-5/8" @ 298'

ABANDONED OIL WELL        GAS WELL        INPUT WELL        SWD No dkt D&A       

OTHER WELL AS HEREINAFTER INDICATED:       

PLUGGING CONTRACTOR: Kelso Casing Pulling  
ADDRESS:        LICENSE: 6050

COMPANY TO PLUG AT: HOUR: 10:00a DAY: 24 MONTH: 7 YR: 1991

PLUGGING PROPOSAL RECEIVED FROM: Mike Kelso

COMPANY NAME: Kelso Casing Pulling PHONE:       

WERE: Tubing out of hole - casing leaks - pull top jt 5-1/2"  
- tie to 8-5/8" & pump 50 sx, 200# hulls, 20 sx gel,  
100# hulls w/water, 150 sx cmt, 100# hulls.

PLUGGING PROPOSAL RECEIVED BY:         
PLUGGING OPERATIONS ATTENDED BY AGENT? ALL (  ) PART (  ) NONE (  ) AUG 2 1991  
08-02-91  
COMPLETED: HOUR: 12:00 DAY: 24 MONTH: 7 YEAR: 1991

ACTUAL PLUGGING REPORT:  
Tubing out of hole & casing leaks - top joint of 5-  
1/2" pulled - tied to 8-5/8" & pumped 50 sx cmt w/200#  
hulls, 20 sx gel, 100# hulls w/water, 150 sx cmt w/100#  
hulls - pump pressure 400# - shut in 100# - used 60/40  
poz 4% gel - old perms up above were squeezed by  
original owner.

REMARKS: Allied #1988 OH 3310-60'

I DID OBSERVE THIS PLUGGING.

**INVOICED**  
DATE 8-13-91  
INV. NO. 32688

Ralph Tittel  
Ralph Tittel (AGENT)

DW