

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-175-20940-00-00  
Spot: SW Sec/Twnshp/Rge: 22-33S-34W  
1320 feet from S Section Line, 3960 feet from E Section Line  
Lease/Unit Name: ETZOLD UNIT Well Number: 3-6  
County: SEWARD Total Vertical Depth: 6425 feet

Operator License No.: 4549  
Op Name: ANADARKO PETROLEUM CORPORATI  
Address: 1201 LAKE ROBBINS DRIVE  
THE WOODLANDS, TX 77380

Production Casing Size: 5.5 feet: 6424 WITH 150 SX CMT  
Surface Casing Size: 8.625 feet: 1635 WITH 775 SX CMT

*208'*

Well Type: EOR UIC Docket No: E24960.5 Date/Time to Plug: 10/07/2003 9:00 AM  
Plug Co. License No.: 7407 Plug Co. Name: EAGLE WELL SERVICE  
Proposal Rcvd. from: RICKY Company: EAGLE WELL SERVICE Phone: (620) 624-1904

Proposed Plugging Method: CIBP @ 5960' WITH 2 SX CMT. TEST CASING. PLUG AT 1670' WITH 50 SX CMT. PLUG AT 685' WITH 50 SX CMT. PLUG AT 40' WITH 15 SX CMT.

Plugging Proposal Received By: JIM HOLLAND WitnessType: Plugging Operations 100% Witnessed (Complete)  
Date/Time Plugging Completed: 10/07/2003 12:00 PM KCC Agent: JIM HOLLAND

Actual Plugging Report:


PBTD 6340'. PERFS AT 6237-6301'. CIBP @ 5960' WITH 2 SX CMT. TEST CASING TO 500 PSIG. HELD OK. 1ST PLUG PULL OUT OF HOLE WITH 5 1/2" TO 1670'. CIRCULATE HOLE WITH MUD & PUMP 50 SX CMT. GOOD CIRCULATION. 2ND PLUG PULL OUT OF HOLE TO 685'. LOAD HOLE & PUMP 50 SX CMT. GOOD CIRCULATION. 3RD PLUG PULL OUT OF HOLE TO 40'. LOAD HOLE & PUMP 15 SX CMT TO SURFACE.

RECEIVED  
OCT 24 2003  
KCC WICHITA

Remarks: USED CLASS A CMT BY EAGLE WELL SERVICE. RECOVERED 1700' OF 5 1/2" CASING.

Plugged through: CSG

District: 01



Signed

*Jim Holland*  
(TECHNICIAN)

INVOICED

DATE 10-24-03

TEL. NO. 2004060673

Form CP-213