

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT REPORT

API Number 15-071-20 229-00-00

200 Colorado Derby Building  
Wichita, KS 67202

Operator's Full Name Cities Service Company

Complete Address 3545 N.W. 58th St. Oklahoma City, Okla. 73112

Lease Name Bollinger "A" (Hiser "A") Well No. 1

Location C-NE <sup>AND 200</sup> Sec. 27 Twp. 19 Rge. 39 (East)(West)

County Greeley Total Depth 2950'

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D&A

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Daco Lease & Well Service

Address Borger Texas License No. 138

Operation Completed: Hour: 4:00 PM Day: 1 Month: June Year: 19 82

Plugging Operations attended by Agent?: All  Part  None

The above well was plugged as follows:

They have 4949' of 4 1/2" production pipe. They plugged back to 2892', perforated at 2852' to 60'. 1st set cast iron plug at 2842' & put 1 bbl of cement on top of it. 2nd plug at ' with 25 bbl of cement. 3rd plug at 500' with 40 bbl of cement. 4th plug at 40'-0' with 10 bbl of cement. They recovered 1520' of 4 1/2" pipe. The cement was pumped through 4 1/2" pipe as they pulled it with hole full of mud. The plugging was accomplished by Daco Lease & well service.

Amount of Surface Casing: 450' of 8 1/8" cement circulated

I hereby certify that the above plugging instructions were given as herein stated.

Signed: Paul A. Luthi  
Conservation Division Agent

I hereby state that I was not present while the above well was being plugged, however, to the best of my knowledge and belief it was plugged as herein stated. A full account for my not being present is as follows:

This well was out of my area and I was to plug in my area.

RECEIVED  
STATE CORPORATION COMMISSION  
JUN - 8 1982  
CONSERVATION DIVISION  
Wichita, Kansas

Signed: Paul A. Luthi  
Conservation Division Agent

INVOICED  
DATE 6-11-82  
NO. 423-W

15-071-20229-00-00

KANSAS DRILLER'S LOG

LEASE: BELLAMY "A" #1  
OWNER: CITIES SERVICE COMPANY  
SPUD: 5-02-81  
COMP: 5-05-81

LOCATION: C NE/4  
SECTION 27-19S-39W  
GREELEY COUNTY, KANSAS  
CASING: 8 5/8" SET @ 450'  
4 1/2" SET @ 2949'

Soil & Clay	40
Clay & Sand	451
Shale	1750
Shale, Salt & Sand	2295
Shale & Shells	2760
Lime & Shale	2950
R.T.D.	2950

STATE OF KANSAS )  
                          ) ss.  
COUNTY OF SEDGWICK )

I, William C. Wakefield, do hereby certify that this is a true and correct Driller's Log on the BELLAMY "A" #1, located C NE/4 SECTION 27-19S-39W, Greeley County, Kansas, as shown by the daily drilling reports.


EARL F. WAKEFIELD, INC.

By William C. Wakefield  
William C. Wakefield

Subscribed and Sworn to before me this 26th Day of May, 1981.

My Appointment Expires:  
October 28, 1984

Carol J. Noel  
Carol J. Noel Notary Public



RECEIVED  
STATE CORPORATION COMMISSION

MAY 17 1982

CONSERVATION DIVISION  
Wichita Kansas