

KANSAS

FORM CP-3
Rev. 1-8-82

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT REPORT

API Number 15-071-20,230-0000

200 Colorado Derby Building
Wichita, KS 67202

Operator's Full Name Cities Service Company

Complete Address 3545 N.W. 58th St Oklahoma City Okla. 73112

Lease Name Chisholm A Well No. 1

Location C-SW/4 Sec. 27 Twp. 19 Rge. 39 (East)(West)

County Greeley Total Depth 2940'

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated _____

Plugging Contractor Daco Leaser Well service

Address Borger Texas License No. L38

Operation Completed: Hour: 10:45AM Day: 27 Month: May Year: 1982

Plugging Operations attended by Agent?: All Part None

The above well was plugged as follows:

The have 2939' of 4 1/2" production pipe cement. They plugged 4 1/2" back to 2916' & perforated at 2835' to 42. 1st plug they set cast iron plug at 2825' & put 1 bbl of cement on top of it. 2nd plug at 1720' with 25 bbl of cement. 3rd plug at 450' with 40 bbl of cement. 4th plug at 40' to 0' with 10 bbl of cement. They recovered 1720' of 4 1/2" pipe. The cement was pumped through 4 1/2" as they pulled it, with the hole full of heavy mud. The plugging was accomplished by Daco Leaser well service.

Amount of Surface Casing: 85 bbl 405' cement circulated

I hereby certify that the above plugging instructions were given as herein stated.

Signed: Paul A. Luthin
Conservation Division Agent

I hereby state that I was not present while the above well was being plugged, however, to the best of my knowledge and belief it was plugged as herein stated. A full account for my not being present is as follows:

This well was out of my area and I had to much to take care of in my area.

Signed: Paul A. Luthin
Conservation Division Agent

INVOICED

DATE 6-1-82

INV. NO. 311-W

RECEIVED
MAY 28 1982
06-02-82
CONSERVATION DIVISION
Wichita Kansas