

KANSAS

Form CP-3

(Rev. 6-4-68)

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

15-071-20062-000
08-02-76
CONSERVATION DIVISION
WICHITA, KANSAS

J. Lewis Brock
Administrator
245 North Water
Wichita, KS 67202

API Number 15 - 071 - 20062 - 000 (of this well)

Operator's Full Name Hughes Seewald

Complete Address 701 1st Nat'l. Bank Bldg., Amarillo, Texas 79101

Lease Name Richardson Well No. 1

Location C SW/4 Sec. 8 Twp. 19 Rge. (E) (W) 39

County Greely Total Depth 2920'

Abandoned Oil Well Gas Well XX Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Sargent Casing Pulling

Address 620 S. Lincoln, Liberal, Kansas License No. 511

Operation Completed: Hour 4 P Day 29 Month 7 Year 1976

The above well was plugged as follows:

Total Depth 2920' 8 5/8 csg set 207' cwc

4 1/2 csg set 2920' cw 150 sk cem.

4 1/2 csg PFS (2852'-2862')

Pumped down 4 1/2 csg with 3 sx gel & water W/100 lbs hulls. (2852'-2700')

Cutoff & recovered 2134# of 4 1/2 csg.

Set 35 sk cmt plug (200'-100') thru 4 1/2 csg.

Heavy mud to 40' -set solid bridge & 10 sk cmt plug to base of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: [Signature]
Well Plugging Supervisor

INVOICED

DATE 8/2/76

INV. NO. 3565-U