

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
245 North Water
Wichita, KS 67202

API Number 15-071-20097-00 (of this well)

Operator's Full Name Dorchester Exploration, Inc.

Complete Address 1204 Vaughn Bldg., Midland, Texas 79701

Lease Name Fecht "C" Well No. 1

Location C NW/4 Sec. 8 Twp. 19 Rge. (E) (W) 39

County Greely Total Depth 2960'

Abandoned Oil Well Gas Well XX Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Sargent Casing Pulling

Address 620 S. Lincoln, Liberal, Kansas License No. 511

Operation Completed: Hour 1 P/ Day 30 Month 7 Year 1976

The above well was plugged as follows:

Total Depth 2960' 8 5/8 csg set 265' cwo

4 1/2 csg set 2956' cw 150 sk cem.

4 1/2 csg PFS (2912'-2922')

Mixed & pumped down 4 1/2 csg with 100 lbs hulls & 10 sk cmt. (2912'-2740')

Cutoff & recovered 2119' of 4 1/2 csg.

Set 35 sx cmt plug (250'-150')

Mud to 45' set rock bridge & 15 sx cmt plug to base of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 8-4-76

INV. NO. 3579-U

Signed: Red Massey
Well Plugging Supervisor

RECEIVED
AUG 15 1976
08-03-76
D. S. C. M.
L. H. C. M.