

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-159-22647-00-00  
Spot: NESENW Sec/Twnshp/Rge: 18-19S-9W  
3566 feet from S Section Line, 3300 feet from E Section Line  
Lease Name: BUCKLEY Well #: 6-18  
County: RICE Total Vertical Depth: 3400 feet

Operator License No.: 4058  
Op Name: AMERICAN WARRIOR, INC.  
Address: 3118 CUMMINGS RD PO BOX 399  
GARDEN CITY, KS 67846

| String | Size  | Depth (ft) | Pulled (ft) | Comments |
|--------|-------|------------|-------------|----------|
| CIBP   |       | 3250       |             |          |
| SURF   | 8.625 | 347        |             | 250 SX   |
| T1     | 2.375 | 3350       |             |          |
| PROD   | 5.5   | 3399       | 2330        | 150 SX   |

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 09/02/2011 12:00 PM  
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.  
Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE Phone: (620) 727-3409

Proposed Plugging Method: SEE BELOW

Plugging Proposal Received By: VIRGIL CLOTHIER Witness Type: PARTIAL  
Date/Time Plugging Completed: 09/02/2011 2:15 PM KCC Agent: VIRGIL CLOTHIER

Actual Plugging Report:

MIRU, CK BOTTOM. SAND PERFS TO 2957' AND CAP WITH 5 SX'S CEMENT. CUT CASING AT 2330' AND PULL TO 1250' AND PUMP 35 SX'S WITH 2% CC AND 100#'S COTTON HULLS. PULL CASING TO 850' AND PUMP 35 SX'S WITH 2% CC AND 100 #'S COTTON HULLS. PULL CASING TO 400' AND CIRCULATE CEMENT TO SURFACE. PULL CASING OUT AND TOP OFF. USED 175 SX'S.

Perfs:

| Top  | Bot  | Thru | Comments |
|------|------|------|----------|
| 3268 | 3270 | CSG  |          |
| 3007 | 3012 | CSG  |          |

Remarks: 60-40 POZ, 4% GEL. QUALITY CEMENT #5254.

Plugged through: CSG

District: 02

Signed Virgil Clothier  
(TECHNICIAN)

RECEIVED  
OCT 03 2011  
Form CP-2/3  
10/27/11

KCC WICHITA

✓