

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-101-21431-00-00  
Spot: NESWSW Sec/Twnshp/Rge: 17-19S-28W  
1000 feet from S Section Line, 4252 feet from E Section Line  
Lease Name: HELEN Well #: 1  
County: LANE Total Vertical Depth: 4703 feet

Operator License No.: 9408  
Op Name: TRANS PACIFIC OIL CORPORATION  
Address: 100 S MAIN STE 200  
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	218		WITH 140 SX CMT
DVT		2500		WITH 400 SX CMT
PKR		4320		
PROD	5.5	4699	0	WITH 200 SX CMT

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 10/14/2011 9:30 AM  
Plug Co. License No.: 6454 Plug Co. Name: CHEYENNE WELL SERVICE, INC.  
Proposal Rcvd. from: GARY SHARP Company: TRANS PACIFIC Phone: (316) 262-3596

Proposed Plugging Method: CMT TO 3910'. RUN TBG TO 1800' CIRCULATE CMT, PULL TBG & TOP OFF. PUMP 50 SX CMT DOWN BACKSIDE IF IT WILL TAKE.

Plugging Proposal Received By: MICHAEL MAIER WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 10/14/2011 11:30 AM KCC Agent: KENNY SULLIVAN

Actual Plugging Report:

CEMENT TO 3910'. PACKER IN HOLE @ 4320'. RAN TBG TO 1800' & CIRCULATED 160 SX CMT. PULLED TBG OUT & TOPPED OFF WITH 20 SX CMT. PUMPED 5 SX CMT DOWN BACKSIDE. PRESSURED TO 150#.

Perfs:

Top	Bot	Thru	Comments
4627	4634		
4340	4346		

RECEIVED  
OCT 24 2011

KCC WICHITA

Remarks: USED 60/40 POZMIX 4% GEL BY CHEYENNE OIL SERVICES.

Plugged through: TBG

District: 01

Signed \_\_\_\_\_

*Kenny M. Sullivan*  
(TECHNICIAN)

RECEIVED  
OCT 18 2011  
KCC DODGE CITY

Form CP-2/3  
10/27/11