

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-097-20639-00-01  
Spot: SWSE Sec/Twnshp/Rge: 26-30S-18W  
660 feet from S Section Line, 1980 feet from E Section Line  
Lease Name: YOST Well #: 1  
County: KIOWA Total Vertical Depth: 5053 feet

Operator License No.: 5030  
Op Name: VESS OIL CORPORATION  
Address: 1700 WATERFRONT PKWY BLDG 500  
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		5013		
SURF	8.625	536		WITH 400 SX CMT
PROD	5.5	5036	2500	WITH 250 SX CMT

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 09/08/2011 1:00 PM  
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.  
Proposal Rcvd. from: JAMIE HARRIS Company: MIKE'S TESTING & SALVAGE, INC Phone: (620) 938-2534

Proposed Plugging Method: SAND BOTTOM TO 4840' WITH 5 SX CMT. PLUG AT 1120' WITH 15 SX GEL & 50 SX CMT. PLUG AT 560' WITH 50 SX CMT. PLUG AT 40' WITH 20 SX CMT.

Plugging Proposal Received By: ERIC MACLAREN Witness Type: NONE  
Date/Time Plugging Completed: 09/08/2011 2:30 PM KCC Agent: ERIC MACLAREN

Actual Plugging Report:

SAND TO 4843' & 5 SX CMT. 1ST PLUG AT 1820' WITH 40 SX CMT. 2ND PLUG AT 1120' WITH 15 SX GEL & 50 SX CMT. 3RD PLUG AT 560' WITH 50 SX CMT. 4TH PLUG AT 40' WITH 40 SX CMT. CMT CIRCULATED.

Perfs:

Top	Bot	Thru	Comments
4890	4894		MARMATON

RECEIVED  
OCT 24 2011

Remarks: \*\*COMPLIANCE ISSUE: DENIED TA. S.I. 10 YRS\*\* USED 60/40 POZMIX 4% GEL BY COPELAND KCC WICHITA

Plugged through: CSG

District: 01

Signed Eric MacLaren  
(TECHNICIAN)

RECEIVED  
OCT 18 2011  
KCC DODGE CITY

Form CP-23  
10/27/11