

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-155-21167-00-00
Spot: W2NESW Sec/Twnshp/Rge: 36-24S-9W
1980 feet from S Section Line, 3630 feet from E Section Line
Lease Name: BREIDENSTEIN Well #: 1
County: RENO Total Vertical Depth: 3941 feet

Operator License No.: 5420
Op Name: WHITE & ELLIS DRILLING, INC.
Address: PO BOX 48848
WICHITA, KS 67201

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	234		165 SXS CMT
PROD	5.5	3939		100 SXS CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 05/20/2011 8:00 AM
Plug Co. License No.: 32983 Plug Co. Name: STEVE'S WELL SERVICE, INC.
Proposal Rcvd. from: DALLAS FLOWERS Company: _____ Phone: (316) 323-3869

Proposed Plugging Method: PER KCC RULES & REGS

Plugging Proposal Received By: DAVID BOLLENBACK Witness Type: PARTIAL
Date/Time Plugging Completed: 06/24/2011 4:00 PM KCC Agent: B. J. HOPE

Actual Plugging Report:

SET CIBP @3770' CAPPED WITH 2 SX OF CEMENT. PERF CASING @ 1400' @ 800' @ 280'. 6/21/11 RAN TUBING INTO 1393' SPOTTED 35 SX OF CEMENT, COULD NOT TAG CEMENT, RAN BACK IN SPOTTED ANOTHER 50 SX CEMENT, TAGGED @ 1350'. PULLED TUBING TO 800' SPOTTED 35 SX OF CEMENT. PULLED TUBING TO 280' PUMPED 15 SX OF CEMENT RAN OUT OF CEMENT. 6/22/11 CIRCULATED TO SURFACE WITH 150 SX OF CEMENT. 6/24/11 CUT HEAD OFF OF CASING TOPPED WITH 15 SX.

Perfs:

Remarks: BASIC ENERTY TICKET #3432

Plugged through: TBG

District: 02

Signed B. J. Hope

(TECHNICIAN) RECEIVED

OCT 24 2011

KCC WICHITA

Form CP-2/3

10/27/11

✓