

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGIN  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-003-01870-00-00  
Spot: NESESWNW Sec/Twnshp/Rge: 13-21S-20E  
3025 feet from S Section Line, 3998 feet from E Section Line  
Lease Name: WEST VAN WINKLE Well #: S-21X  
County: ANDERSON Total Vertical Depth: 660 feet

Operator License No.: 34170  
Op Name: SIRIUS ENERGY CORP.  
Address: 526 COUNTRY PL, SOUTH  
ABILENE, TX 79606

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	6	20		
PROD	2	609		

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 07/14/2011 12:00 AM  
Plug Co. License No.: 99998 Plug Co. Name: COMPANY TOOLS  
Proposal Rcvd. from: RANDY TETER Company: \_\_\_\_\_ Phone: (785) 448-8571

Proposed Plugging Method: RUN 3/4 INCH PIPE APPROX. 650 FEET AND FILL 2 INCH PIPE WITH APPROX. 20 SACKS. RUN 1 INCH PIPE TO BOTTOM AND FILL BACKSIDE TO SURFACE WITH APPROX. 100 SACKS.

Plugging Proposal Received By: LEVI SHORT Witness Type: PARTIAL  
Date/Time Plugging Completed: 07/14/2011 12:00 AM KCC Agent: LEVI SHORT

Actual Plugging Report: RUN 3/4 INCH INSIDE 2 INCH CASING TO 609 FEET AND FILL WITH 18 SACKS OF PORTLAND CEMENT TO SURFACE. RUN 1 INCH OUTSIDE TO BOTTOM AND PUMP 86 SACKS OF CEMENT. PULL PIPE AND TOP OFF WELL. PUMP TOTAL OF 104 SACKS OF CEMENT.

RECEIVED  
LS  
KCC Chanute Dist. #3

Perfs:

Remarks:  
Plugged through: TBG

District: 03 Signed [Signature]  
(TECHNICIAN)

RECEIVED ✓ Form CP-2/3  
OCT 24 2011 10/27/11  
KCC WICHITA