

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-145-21653-00-00
Spot: NESWSESE Sec/Twnshp/Rge: 1-22S-17W
555 feet from S Section Line, 705 feet from E Section Line
Lease Name: WOODS TRUST Well #: 1-1
County: PAWNEE Total Vertical Depth: 4030 feet

Operator License No.: 31725
Op Name: SHELBY RESOURCES LLC
Address: 445 UNION BOULEVARD SUITE 208
LAKEWOOD, CO 80228

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	1022		

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 10/16/2011 2:00 PM
Plug Co. License No.: 5142 Plug Co. Name: STERLING DRILLING COMPANY
Proposal Rcvd. from: SHANE DOWNS Company: STERLING DRILLING COMPANY Phone: (620) 672-9508

Proposed Plugging Method: 1ST PLUG AT 3870' WITH 50 SX CMT. 2ND PLUG AT 1050' WITH 50 SX CMT. 3RD PLUG AT 540' WITH 50 SX CMT. 4TH PLUG AT 60' WITH 20 SX CMT. 5TH PLUG TO CIRCULATE RAT HOLE WITH 30 SX CMT. 6TH PLUG TO CIRCULATE MOUSE HOLE WITH 20 SX CMT.

Plugging Proposal Received By: ERIC MACLAREN WitnessType: NONE
Date/Time Plugging Completed: 10/16/2011 4:00 PM KCC Agent: ERIC MACLAREN

Actual Plugging Report:

Perfs:

1ST PLUG AT 3870' WITH 50 SX CMT. 2ND PLUG AT 1050' WITH 50 SX CMT. 3RD PLUG AT 540' WITH 50 SX CMT. 4TH PLUG AT 60' WITH 20 SX CMT. 5TH PLUG TO CIRCULATE RAT HOLE WITH 30 SX CMT. 6TH PLUG TO CIRCULATE MOUSE HOLE WITH 20 SX CMT.

RECEIVED
OCT 24 2011
KCC WICHITA

Remarks: USED 60/40 POZMIX 4% GEL BU QUALITY CEMENTING.

Plugged through: DP

District: 01

Signed Eric MacLaren
(TECHNICIAN)

RECEIVED
OCT 18 2011
KCC DODGE CITY

Form CP-23
10/27/11