

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-195-21387-00-00
Spot: SESWNW Sec/Twnshp/Rge: 29-15S-21W
2926 feet from S Section Line, 4359 feet from E Section Line
Lease Name: UNREIN Well #: 2
County: TREGO Total Vertical Depth: 4380 feet

Operator License No.: 5086
Op Name: PINTAIL PETROLEUM, LTD.
Address: 225 N MARKET STE 300
WICHITA, KS 67202

| String | Size | Depth (ft) | Pulled (ft) | Comments |
|--------|-------|------------|-------------|----------|
| SURF | 8.625 | 263 | 0 | 170 SX |
| PROD | 5.5 | 4378 | 0 | 75 SX |

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 10/20/2011 10:00 AM
Plug Co. License No.: 31627 Plug Co. Name: WHITETAIL CRUDE, INC
Proposal Rcvd. from: BILLY BRINEY Company: WHITETAIL CRUDE, INC Phone: (785) 798-5116

Proposed Plugging Method: Ordered 400 sxs 60/40 pozmix - 4% gel - 400# hulls - 10 sxs gel spacer.
Shoot perfs at 2400' - 900' - 255'.

Plugging Proposal Received By: MARVIN MILLS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 10/20/2011 2:45 PM KCC Agent: MARVIN MILLS

Actual Plugging Report:

Ran tubing to 4320' - pumped 12 sxs gel - followed with 50 sxs cement and 100# hulls.
Pulled tubing to 2506' - pumped 240 sxs cement - good circulation of cement.
Pulled tubing out - tied onto backside - pumped 30 sxs cement.
S.I.P. 605#. Pumped 25 sxs cement to top off 5 1/2" casing - full.

Perfs:

| Top | Bot | Thru | Comments |
|------|------|------|----------|
| 4322 | 4323 | | CHEROKEE |
| 4309 | 4310 | | CHEROKEE |
| 4265 | 4268 | | CHEROKEE |
| 4255 | 4259 | | CHEROKEE |

Remarks: SWIFT CEMENTING COMPANY.

Plugged through: TBG

District: 04

Signed _____

(TECHNICIAN)

CM

RECEIVED
OCT 24 2011
KCC WICHITA

Form CP-2/3

10/27/11

OCT 20 2011