

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-119-21128-00-00
Spot: SWNENENW Sec/Twnshp/Rge: 13-34S-29W
4765 feet from S Section Line, 3214 feet from E Section Line
Lease Name: 7U RANCH Well #: 1-13
County: MEADE Total Vertical Depth: 6500 feet

Operator License No.: 30604
Op Name: RAYDON EXPLORATION, INC.
Address: 1601 NW EXPRESSWAY, STE 1300
OKLAHOMA CITY, OK 73118

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		5780		WITH 2 SX CMT
SURF	8.625	1656		WITH 555 SX CMT
COND	20	40		WITH 10 SX CMT
PROD	4.5	6500	4406	WITH 305 SX CMT

Well Type: OG UIC Docket No: _____ Date/Time to Plug: 10/19/2011 10:00 AM
Plug Co. License No.: 32833 Plug Co. Name: SARGENT LILLARD CASING PULLING, INC.
Proposal Rcvd. from: DAVID E. RICE Company: RAYDON EXPLORATION Phone: (620) 624-0156

Proposed Plugging Method: CIBP @ 5780' WITH 2 SX CMT. PLUG AT 1690' WITH 50 SX CMT. IN & OUT SURFACE CSG, PLUG AT 600' WITH 50 SX CMT. PLUG AT 40' WITH 15 SX CMT.

Plugging Proposal Received By: KEN JEHLIK WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 10/19/2011 3:00 PM KCC Agent: KENNY SULLIVAN

Actual Plugging Report:

SET CIBP@ 5780' WITH 2 SX CMT. 1ST PLUG AT 1690' WITH 50 SX CMT. 2ND PLUG AT 600' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 10 SX CMT. CMT CIRCULATED.

Perfs:

Top	Bot	Thru	Comments
5827	5831		CHESTER LIME

Remarks: USED COMMON CEMENT BY SARGENT & LILLARD.

Plugged through: CSG

RECEIVED

OCT 24 2011

KCC WICHITA

District: 01

RECEIVED

OCT 21 2011

KCC DODGE CITY

Signed

(TECHNICIAN)

Form CP-2/3

10/27/11