

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-195-22118-00-02
Spot: NWSESE Sec/Twnshp/Rge: 27-15S-21W
990 feet from S Section Line, 990 feet from E Section Line
Lease Name: J & L LAND A Well #: 1
County: TREGO Total Vertical Depth: 4138 feet

Operator License No.: 31120
Op Name: PELICAN HILL OIL & GAS, INC.
Address: 1401 N EL CAMINO REAL SUITE 207
SAN CLEMENTE, CA 92672

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	292	0	w/unknown sxs cmt
PROD	5.5	4340	0	w/unknown sxs cmt

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 10/12/2011 10:45 AM
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY
Proposal Revd. from: HAROLD BELLERIVE Company: PELICAN HILL OIL & GAS, INC. Phone: (785) 635-4531

Proposed Plugging Method: Ordered 475 sxs 60/40 pozmix - 4% gel - 400# hulls.

Plugging Proposal Received By: RAY DINKEL Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 10/12/2011 4:00 PM KCC Agent: RAY DINKEL

Actual Plugging Report:

Ran tubing to 3800' - pumped 100 sxs cement with 200# hulls.
Pulled tubing to 2800' - pumped 100 sxs cement with 200# hulls.
Pulled tubing to 1800' - pumped 100 sxs cement - cement circulated.
POOH. Hooked to casing and pumped 30 sxs cement.
Max. P.S.I. 1000#. S.I.P. 500#.
Braden head was found to be full of cement from earlier plug job.

Perfs:

Top	Bot	Thru	Comments
3849	3850		
3844	3845		

Remarks: ALLIED CEMENTING COMPANY-TICKET #35813.

Plugged through: TBG

District: 04

Signed

Ray A. O. K. P.

(TECHNICIAN)

CM

RECEIVED

OCT 24 2011

KCC WICHITA

Form CP-2/3

10/27/11

OCT 18 2011