

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-135-25295-00-00  
Spot: SWSENWNE Sec/Twnshp/Rge: 8-16S-22W  
1181 feet from N Section Line, 1740 feet from E Section Line  
Lease Name: HOGSETT Well #: 1-8  
County: NESS Total Vertical Depth: 4440 feet

Operator License No.: 5144  
Op Name: MULL DRILLING COMPANY, INC.  
Address: 1700 N WATERFRONT PKWY BLDG 12  
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	220		

Well Type: DH UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 10/05/2011 12:30 AM  
Plug Co. License No.: 33575 Plug Co. Name: WW DRILLING, LLC  
Proposal Rcvd. from: JAY SCHNEIDER Company: WW DRILLING, LLC Phone: (785) 743-6774

Proposed Plugging Method: IST PLUG AT 1760' WITH 50 SX CMT. 2ND PLUG AT 1110' WITH 80 SX CMT. 3RD PLUG AT 600' WITH 50 SX CMT. 4TH PLUG AT 240' WITH 50 SX CMT. 5TH PLUG AT 60' WITH 20 SX CMT. 6TH PLUG TO CIRCULATE RAT HOLE WITH 30 SX CMT. NO MOUSE HOLE.

Plugging Proposal Received By: ERIC MACLAREN WitnessType: NONE  
Date/Time Plugging Completed: 10/05/2011 2:30 AM KCC Agent: ERIC MACLAREN

Actual Plugging Report:

Perfs:

IST PLUG AT 1760' WITH 50 SX CMT. 2ND PLUG AT 1110' WITH 80 SX CMT. 3RD PLUG AT 600' WITH 50 SX CMT. 4TH PLUG AT 240' WITH 50 SX CMT. 5TH PLUG AT 60' WITH 20 SX CMT. 6TH PLUG TO CIRCULATE RAT HOLE WITH 30 SX CMT. NO MOUSE HOLE.

Remarks: USED 60/40 POZMIX 4% GEL 1/4# FLO SEAL BY CONSOLIDATED.

Plugged through: DP

RECEIVED  
OCT 24 2011  
KCC WICHITA

District: 01

Signed Eric MacLaren  
(TECHNICIAN)

RECEIVED  
OCT 17 2011  
KCC DODGE CITY

10/27/11  
Form CP-2/3