

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-081-00384-00-00
Spot: NENENESW Sec/Twnshp/Rge: 20-29S-32W
2490 feet from S Section Line, 2790 feet from E Section Line
Lease Name: KELMAN Well #: 1
County: HASKELL Total Vertical Depth: 2730 feet

Operator License No.: 32787
Op Name: KANSAS NATURAL GAS OPERATING, I
Address: 1200 MAIN ST PO BOX 818
HAYS, KS 67601

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		2704		
SURF	10.75	597		WITH 400 SX CMT
PROD	7	2721	0	WITH 700 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 10/03/2011 11:30 AM
Plug Co. License No.: 33338 Plug Co. Name: ORR ENTERPRISES, INC.
Proposal Revd. from: STEVE LEHNING Company: KANSAS NATURAL GAS Phone: (620) 675-8185

Proposed Plugging Method: CIBP @ 2600' & 10 SX CMT. CIRCULATE MUD. PLUG AT 1850' WITH 50 SX CMT. PLUG AT 630' CIRCULATE CMT TO SURFACE. CHECK BACKSIDE.

Plugging Proposal Received By: STEVE DURRANT WitnessType: NONE
Date/Time Plugging Completed: 10/03/2011 5:00 PM KCC Agent: STEVE DURRANT

Actual Plugging Report:

1ST PLUG TIHWT TO 2620'. FILL HOLE WITH MUD. THEN MIX & PUMP 30 SX CMT. EST TOC @ 2445'. 2ND PLUG PTT 1850'. MIX & PUMP 45 SX CMT. 3RD PLUG PTT 630'. MIX & PUMP 110 SX CMT. CIRCULATE CMT TO SURFACE. 4TH PLUG POOH. TOP OFF 7" WITH 10 SX CMT. 5TH PLUG RUN 2" INSIDE ANNULUS TO 18'. PUMP 10 SX CMT.

Perfs:

Top	Bot	Thru	Comments
2670	2692		

Remarks: USED CLASS C CMT BY ORR ENTERPRISES.

Plugged through: TBG

District: 01

Signed

Steve Durrant

(TECHNICIAN)

RECEIVED

OCT 17 2011

KCC DODGE CITY

RECEIVED
OCT 24 2011

KCC WICHITA

Form CP-2/3

10/27/11