

15-035-01476-00-00

412 Union National Bk Bldg., Wichita, Kansas

JONES  
NE 32 E  
R. 5E

Operator:  
Merlin Hickman


JONES BROS. DRILG. CO.  
Chance No. 2.

SEC. 21  
NE SW NE

K & S LIBRARY

Total Depth. 3084'  
Comm. 9-18-39 Comp. 11-13-39  
Shot or Treated.  
Contractor.  
Issued, 2-10-40

County. Cowley



CASING:  
13 3/8"  
10"  
8"

460' 65/8" 2560'  
1102' 5 1/2" 3022'  
2062'

Elevation. 1291

Production. Pct. 296 B.

Figures Indicate Bottom of Formations.

cellar	12	shale lgt	1112	shale	2668
slate	68	lime	1117	sand	2728
shale	120	slate	1130	shale	2736
lime	135	lime	1150	lime	2748
slate	145	shale sdy	1155	shale	2752
red rock	155	shale lgt	1230	lime	2767
lime	160	lime	1275	shale	2760
slate	172	shale & shells	1300	lime	2776
lime	176	lime	1350	slate	2792
red rock	185	slate	1358	lime	2850
slate	195	lime	1375	shale	2852
lime	210	slate	1380	lime	2856
lime brkn	230	lime	1425	shale sdy	2930
shale blue	235	shale sdy	1450	shale & shells	2940
red rock	245	shale lgt	1480	slate blue	3010
shale	255	sand	1518	sdv shale lgt	3021
lime shells & slate	280	slate	1525	sdv shale	3046
lime	300	lime	1532	sand- sh oil	3049 1/2
slate & shells	307	sand	1550	sand- free oil & gas	3061
slate gy	312	slate	1565	sand, nice increase oil	
lime	318	sand	1580	& gas, fillup &	
red rock	321	shale lgt	1587	flowed	3054
lime	335	slate	1625	Total Depth.	
shale	340	lime shells	1645		
lime	365	lime	1647		
shale	375	slate	1660	2 FWH 130-38	
red rock	400	red rock	1695	3 FWH 745-63	
lime sdy	470	shale	1708	HFW 1050-65	
shale	475	lime	1725	HFW 1480-95	
lime	540	shale lgt	1745	Wtr at 2000	
slate	555	red rock	1750	HFW 2157-65	
lime	575	lime	1754	SEWPH 2575-83	
slate	580	shale	1785	& BWPE 2700-28	
lime	585	lime	1800		
slate	605	shale, blue slate	1928	Gas 438-42, little gas 685	
red rock	610	lime	1932	oil & gas 3049 1/2-51	
slate	630	slate	1965	increase gas & oil 3051-54	
lime	635	lime	1970		
slate	680	slate	1992		
lime	705	sand	2057		
slate	745	slate	2137		
sand	783	lime	2140		
slate	815	slate	2157		
lime	820	sand	2189		
shale	835	slate dk	2208		
lime	840	shale	2315		
shale	870	shale lgt	2380		
lime	885	sand	2400		
slate	890	lime	2410		
lime	915	shale sdy	2416		
slate	940	lime	2420		
lime	950	shale lgt	2430		
slate	955	sand	2470		
lime	970	lime sdy	2485		
shale	985	slate blue	2550		
lime	990	lime, K.C.	2560		
shale	1005	shale blk	2563		
lime	1010	lime	2596		
shale	1020	shale	2602		
sand	1053	lime	2604		
slate	1080	shale	2610		
lime	1100	lime	2650		

RECEIVED  
NOV 01 2011  
KCC WICHITA