

KCC OIL/GAS REGULATORY OFFICES

Date: 10/13/11

District: 1

Case #: _____

- New Situation
- Response to Request
- Follow-Up

- Lease Inspection
- Complaint
- Field Report

Operator License No: 4767
 Op Name: Ritchie Exploration, Inc.
 Address 1: 8100 E. 22nd St. N. #700
 Address 2: Box 783188
 City: Wichita
 State: KS Zip Code: 67278 -3188
 Operator Phone #: (316) 691-9500

API Well Number: 15-057-20752-00-00
 Spot: SW-NW Sec 10 Twp 28 S Rng 22 E / W
 1930 Feet from N / S Line of Section
 550 Feet from E / W Line of Section
 GPS: Lat: 37.62581 Long: 99.72007 Date: 10/13/11
 Lease Name: Derstein 10BC Well #: 1
 County: Ford

Reason for Investigation:

Company requested a state witness to the alternate II cementing job.

Problem:

Alternate II cementing requirements have not been met.

Persons Contacted:

Gary Rowe.

Findings:

8 5/8" was set @ 356' with 250 sx cement. 5 1/2" was set @ 5197' with 175 sx cement on primary cement job. Company opened port collar @ 1338'. Basic Energy Services, L.C. pumped 400 sx of 60/40 poz, 6% gel, 1/4# floseal cement, with 100# hulls, circulating 20 sx to the pit. Closed port collar.

Action/Recommendations:

Follow Up Required Yes No

Date: _____

None. Alternate II cementing requirements have been met.
GPS converted footages are 1944' FNL & 568' FWL.

RECEIVED
OCT 24 2011
KCC WICHITA

Verification Sources:

Photos Taken: 0

- RBDMS
- T-I Database
- Other: On-site witness
- KGS
- District Files
- TA Program
- Courthouse

By: Eric McLaren
Eric McLaren

Retain 1 Copy District Office
Send 1 Copy to Conservation Division

RECEIVED
OCT 18 2011
KCC DODGE CITY

Form: _____