

TO:  
STATE CORPORATION COMMISSIO  
CONSERVATION DIVISION - PLUGGIN  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 6720

API Well Number: 15-019-22027-00-00  
Spot: SWNESENW Sec/Twnshp/Rge: 36-34S-11E  
1830 feet from N Section Line, 2998 feet from E Section Line  
Lease Name: O K SPURLOCK Well #: 7  
County: CHAUTAUQUA Total Vertical Depth: 1191 feet

Operator License No.: 8387  
Op Name: CUSTER, BILL I.  
Address: 2138 DALTON RD  
PERU, KS 67360

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	150		17 SX
PROD	4.5	1193		

Well Type: EOR UIC Docket No: E00289.1 Date/Time to Plug: 10/19/2011 12:00 PM  
Plug Co. License No.: 32884 Plug Co. Name: ELMORE'S, INC.  
Proposal Rcvd. from: JOHN ELMORE Company: Phone: (620) 249-2519

Proposed Plugging Method: RUN 1" TO 1160' GEL HOLE SPOT 10 SKS CEMENT ON BOTTOM. PULL 1" UP TO 700' SPOT 5 SKS CEMENT PLUG PULL UP TO 350' CEMENT TO SURFACE.

Plugging Proposal Received By: DUANE SIMS WitnessType: NONE  
Date/Time Plugging Completed 10/19/2011 3:00 PM KCC Agent: DUANE SIMS

Actual Plugging Report:

Ran 1" to 1175' gelled hole and spotted 10 sack plug. Pulled up to 700' and spotted 5 sack plug. Pulled up to 350' and circulated cement to surface. Pulled 1" and topped well off. A total of 50 sacks of cement were used to plug this well.

Perfs:

Top	Bot	Thru	Comments
1161	1169		

RECEIVED

OCT 20 2011 DAS

KCC Chanute Dist. #3

Remarks: PLUGGED DUE TO FAILED MIT

Plugged through: TBG

District: 03

Signed Dal

(TECHNICIAN)

cc to nrc 10/28/11

RECEIVED

Form CP-2/3

OCT 28 2011

11/03/11

KCC WICHITA