

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-189-22751-00-00  
Spot: SESENW Sec/Twnshp/Rge: 20-31S-35W  
2307 feet from N Section Line, 2329 feet from W Section Line  
Lease Name: CULLISON Well #: 20 #2  
County: STEVENS Total Vertical Depth: 6200 feet

Operator License No.: 5278  
Op Name: EOG RESOURCES, INC.  
Address: 3817 NW EXPRESSWAY STE 500  
OKLAHOMA CITY, OK 73112

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		5949		WITH 5 SX CMT
SURF	8.625	1707		WITH 500 SX CMT
PROD	5.5	6192	2540	WITH 135 SX CMT

Well Type: DH UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 10/14/2011 12:00 AM  
Plug Co. License No.: 33338 Plug Co. Name: ORR ENTERPRISES, INC.  
Proposal Rcvd. from: RONNIE ORR Company: ORR ENTERPRISES, INC. Phone: (580) 251-9618

Proposed Plugging Method: CIBP @ 5949' WITH 5 SX CMT. PLUG AT 1737' WITH 120 SX CMT. PLUG AT 630' WITH 60 SX CMT. PLUG AT 60' WITH 20 SX CMT.

Plugging Proposal Received By: KEN JEHLIK WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 10/18/2011 12:00 AM KCC Agent: JACK MACLASKEY

Actual Plugging Report:

SET CIBP @ 5949' WITH 5 SX CMT. RIH W/TBG TO 1741' & PUMPED 120 SX CMT. POOH TO 600' & PUMPED 60 SX CMT. FILLED 8 5/8" CASING FROM 60' TO SURFACE WITH 20 SX CMT

Perfs:

Top	Bot	Thru	Comments
5999	6017		ST GENEVIEVE

RECEIVED  
OCT 28 2011  
KCC WICHITA

Remarks: USED CLASS C CEMENT BY ORR ENTERPRISES

Plugged through: CSG

District: 01

Signed

Jack MacLaskey  
(TECHNICIAN)

RECEIVED

OCT 21 2011

KCC DODGE CITY

Form CP-273  
11/03/11