

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-173-20694-00-00
Spot: W2NWNWSW Sec/Twnshp/Rge: 13-29S-1E
2310 feet from S Section Line, 105 feet from W Section Line
Lease Name: GLASER Well #: 2-13
County: SEDGWICK Total Vertical Depth: 3489 feet

Operator License No.: 4419
Op Name: BEAR PETROLEUM, LLC
Address: PO BOX 438
HAYSVILLE, KS 67060

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	254		cmt. w/180 sx
COND	10.37	84		cmt. w/125 sx
PROD	4.5	3486	2150	

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 10/06/2011 12:00 PM
Plug Co. License No.: 3004 Plug Co. Name: GRESSEL OILFIELD SERVICE, LLC
Proposal Revd. from: JOE BURNETT Company: BEAR PETROLEUM Phone: (620) 960-5612

Proposed Plugging Method: AS PER KCC RULES AND REGULATIONS, SAND OFF TO 3436' AND CAP WITH 4 SX. CIRC. FROM 50' BELOW SURFACE CASING TO SURFACE, CHECK FOR CMT. BETWEEN CONDUCTOR PIPE AND SURFACE PIPE.

Plugging Proposal Received By: DUANE KRUEGER Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 10/06/2011 12:00 PM KCC Agent: DAN FOX

Actual Plugging Report:

ON SEPT. 30TH GRESSEL OILFIELD SERVICE, INC. RIH W/WORK STRING CIRC. HOLE CLEAN @ 3486' FILLED 4 1/2 WITH 50 GAL. OF SAND BACK TO 3410' CAPPED SAND W/4 SX OF CMT. W/DUMP BALER. PULLED PIPE FOR NEXT TWO DAYS, AND LAID OUT 2150' OF PRODUCTION CASING. COPELAND ACID AND CEMENT CAME BACK IN ON OCTOBER 6, AND RAN IN AT 310' CIRC. 160 SX OF CMT TO SURFACE. GRESSEL DID DIG OUT CONDUCTOR PIPE CUT HOLE FOR INSPECTION AND IT LOOKED LIKE THERE WAS GOOD CEMENT BETWEEN CONDUCTOR PIPE AND SURFACE PIPE.


Perfs:

Remarks: COPELAND ACID AND CEMENT TICKET #37796

Plugged through: TBG

District: 02

Signed



(TECHNICIAN)

RECEIVED Form CP-2/3
NOV 02 2011 11/02/11
KCC WICHITA

✓